ERTIFIED ESTING ABORATORIES

Architectural Division • 7252 Narcoossec Rd. • Orlando, FL 32822

(407) 384-7744 • Fax (407) 384-7751

Web Site: www.ctlarch.com

E-mail: ctlarch.com

Report No.: CTLA 2037W-1 DC Not. No.: CTL 10011

CTL Certification #: 08-0528.05

Date: June 28, 2010

Test Dates: June 21st – 26th, 2010

Test Requested By: Ingersoll Rand

9017 Blue Ash Rd.

Cincinnati, Ohio 45242

TAS 201 (Lg. Missile), TAS 202 (with deviations, no water test) & TAS 203 **Tests Conducted:**

Design Pressures:

Specimen 1 (TAS 202) - Outswing

- 70.0 psf. + 80.0 psf.

Specimen 2

(TAS 202) - Inswing

- 80.0 psf. +70.0 psf.

Specimen 3 & 4

(TAS 201, TAS 203)

- 70.0 psf. +70.0 psf.

(1) DESCRIPTION OF SERIES

Model Designation:

SZ Series 3070 Steel Commercial Flush Door, 18 gauge

Overall Size:

All Specimens - (Frame) 40.00" wide x 86.00" high x 5.75"" deep.

Configuration:

All Specimens - X

No. & Size of Panels:

All Specimens - (1) Slab 35.79" wide x 83.19" high.

(2) MATERIAL CHARACTERISTICS

Frame Material:

All Specimens

ASTM A-366 16 Ga. Steel, cold rolled as stated by manufacturer

Frame Construction:

All Specimens

Cold rolled steel measuring 2.0" wide face x 5.75" deep x 4.875" throat opening. Mitered corner tab and slot construction. Extruded aluminum threshold measuring

0.500" high x 5" wide x 36" long coped to fit into main frame and secured with

three (3) $\#12 \times 1.50$ " wood screws.

Page 2 of 8 Report #:

Ingersoll Rand CTLA 2037W-1

Slab Construction:

All Specimens

Single slab measure 35.79" x 83.19" x 1.75". 18 Ga. Galvanized steel skins. Polystyrene core laminated to both inside faces. Vertical edges square with a continuous mechanical seam. Top and bottom rails contained 16 GA. steel channels measuring .688" x 1.660" x 35.66" long, spot welded to face sheets nominally 2" from each end and 6" on center thereafter. Lock reinforcement is 14 Ga. and 8 Ga. hinge reinforcements.

Glazing:

N/A

Weather-stripping:

All Specimens

QTY

DESCRIPTION

LOCATION

One (1) Strip

PS-074 Weather-strip

Frame Head Frame Jambs

One (1) Strip

PS-074 Weather-strip

Length of threshold

One (1) Strip One (1) piece

Fas-seal door sweep two (2) fin

Bulb vinyl bumper basket .250" o.d.

Slab bottom

Hardware:

All Specimens

QTY

DESCRIPTION

LOCATION

Three (3)

Ives 5BB1 hinges 4.5" x 4.5" x .134" thick with

four (4) .210" dia. X .525" self threading Phillips head countersunk screws to frame and

four (4) Phillips head countersunk screws to the

leaf.

Three in each frame jamb

measuring from rabbet in head to center of hinge at 9.75",

41.69" and 73.625"

Six (6)

Wire hinge spacer.

One behind each hinge on door

leaf.

One (1)

Falcon MA series mortise lock 3/4" latch throw

Door Slab

(no deadbolt)

One (1)

National Guard 950A Threshold w/bumper.

Frame Sill.

Reinforcement:

All Specimens

OTY

DESCRIPTION

One (1)

Mortise lock reinforcement, 14 GA

galvanized steel

Three (3)

Hinge reinforcement, 8 GA

galvanized steel measuring 1.25" x

8" long.

Three (3)

Hinge reinforcement, 7 Ga. steel

measuring 1.23" x 9.19" long.

LOCATION

Door leaf lock stile

Door leaf hinge stile

Page 3 of 8 Report #: Ingersoll Rand CTLA 2037W-1

Weep holes:

N/A

Sealant:

All Specimens

Latex caulking as needed to seal unit into rough opening.

INSTALLATION:

Screws and Method of Attachment:

All Specimens

Specimens were tested in wooden test buck, installed with eight (8) 3/8 x 4" lag

bolts (4 per jamb) and three (3) #12 x 1.50" wood screws.

Head:

None

Sill:

Three (3) #12 x 1.5" wood screws located 6.5", 18", 29.5"

Jambs: Eight (8) 3/8" x 4" lag bolts. Four (4) in each Jamb, located

measuring from bottom to top at 4", 19.97", 51.9", and 80".

Page 4 of 8 Report #: Ingersoll Rand CTLA 2037W-1

Performance Test Results


Test Sequence: TAS 202

1. Air Infiltration ASTM 283-91
2. ½ Test Pressure Positive ASTM E330-02
3. ½ Test Pressure Negative ASTM E330-02
4. Design Pressure Positive ASTM E330-02

5. Design Pressure Negative6. Full Test pressure PositiveASTM E330-02ASTM E330-02

7. Full Test Pressure Negative ASTM E330-02

Deflection Gauges locations



X

Deflection was measured with two (2) 5" CDI Dial Indicators

Location #1 2" above lock. Location # 2 Mid-span of fasteners in jamb.

AIR INFILTRATION

Air Infiltration Tests were conducted in accordance with TAS 202-94

Air @ 1.57 psf. Specimen 1 Actual .10 cfm/ft²

Allowable .34 cfm/ft²

Specimen 2

.11 cfm/ft²

.34 cfm/ft²

STATIC AIR PRESSURE TESTS

Static Tests were conducted in accordance with TAS 202-94


Specimen 1 - Outswing

Specimen 1 Outs	7 **** 6			1925 1925 1935	5 6 4	A 11 T T
Range of test	Time (Sec.)	Load (psf.)	Loc.	Deflection	Perm. Set	<u>Allowable</u>
Positive loads	(Design Press	sure + 80.0 psf.)			
1/2 Test	30	60				
Design	30	80	Loc. 1	0.320"		
· ·			Loc. 2	0.142"		
Test	30	120	Loc. 1		0.027"	0.333"
			Loc. 2		0.027"	0.128"
Negative loads	(Design Press	sure – 70.0 psf.)			
1/2 Test	30	52.5				
Design	30	70	Loc. 1	0.780"		
· ·			Loc. 2	0.091"		
Test	30	105	Loc. 1		0.280"	0.333"
			Loc. 2		0.034"	0.128"

All Permanent set numbers are gross numbers

Location (1) - Max. allowable Perm. Set after test load (0.4% of 83.25" span) = 0.333"

Location (2) - Max. allowable Perm. Set after test load (0.4% of 32.0" span) = 0.128"



Page 5 of 8 Report #: Ingersoll Rand CTLA 2037W-1

Performance Test Results (Continued)

STATIC AIR PRESSURE TESTS (Continued)

Specimen 2 - Inswing

Range of test	Time (Sec.)	Load (psf.)	Loc.	Deflection	Perm. Set	Allowable
Positive loads	(Design Press	sure $+60.0$ psf.) —			
1/2 Test	30	60				
Design	30	80	Loc. 1	0.805"		
-			Loc. 2	0.094"		
Test	30	120	Loc. 1		0.270"	0.333"
			Loc. 2		0.035"	0.128"
Negative loads	(Design Press	sure – 80.0 psf.))			
1/2 Test	30	45				
Design	30	60	Loc. 1	0.332"		
			Loc. 2	0.145"		
Test	30	90	Loc. 1		0.028"	0.333"
			Loc. 2		0.026"	0.128"

All Permanent set numbers are gross numbers

Location (1) - Max. allowable Perm. Set after test load (0.4% of 83.25" span) = 0.333" Location (2) - Max. allowable Perm. Set after test load (0.4% of 32.0" span) = 0.128"

Specimen 1	Title of Test Forced Entry Resistance Load peak was 30 seconds	Method AAMA 1304 -02	Passed	300 lbs
Specimen 2	Forced Entry Resistance Load peak was 30 seconds	AAMA 1304 -02	Passed	300 lbs

Note: At the conclusion of testing, there was no opening thru which access to the interior hardware, or locking devices could be gained. In addition there was no opening which allowed for entrance into the specimen tested. The leaf remained locked, closed and no locks or hinges disengaged.

Page 6 of 8

Ingersoll Rand CTLA 2037W-1

Report #:

Performance Test Results (Continued)

Impact Test: Large Missile

Impact tests were conducted in accordance with TAS 201-94


Each specimen was impacted with an 8 ft., 9 lb. Southern yellow pine 50mm x 100mm (2" x 4") at the following locations:


Note: Specimen 3 (Outswing) & 4 (Inswing)

X measurement from left edge of specimen.

Y measurement from top edge of test specimen.

Type and weight of missile: #2 Southern Yellow Pine 2x4, Length approx. 89-5/16" & 9 lb.





Specimen #	Impact No.	Speed Ft/Sec.	X Meas.	Y Meas.
3	1	49.3	20.00"	41.50"
3	2	49.9	33.50"	75.00"
4	1	49.1	20.00"	42.00"
4	2	50.3	33.00"	76.00"

Result: None of the impacts penetrated the specimen.



Page 7 of 8

Ingersoll Rand CTLA 2037W-1

Report #:

Performance Test Results (Continued)

Fatigue Loading Test

Cycle tests were conducted in accordance with TAS 203

Specimen 3 & 4

Positive loads

Design Pressure + 70.0 psf.

Range of Test	Actual Load (psf.)	# of Cycles	Cycles/min.
+ .0 to 0.5	35.0	600	56
+.0 to 0.6	.42.0	70	56
+.0 to 1.3	91.0	1	

671 cycles completed

Deflection Set 0.00"

Negative Loads

Design Pressure - 70.0 psf.

Range of Test	Actual Load (psf.)	# of Cycles	Cycles/min.	
+.0 to 0.5	35.0	600	56	
+.0 to 0.6	42.0	70	56	
+ .0 to 1.3	91.0	1		
				Defle

671 cycles completed

Deflection Set 0.500"

Result: Specimen showed no resultant failure or duress after cycle test. No failure of fasteners. There were no cracks longer than 5" x 1/16" through which air could pass observed.

The results obtained and reported apply only to the specimens tested.

Comment:

Nominal 2 mil polyethylene film was used to seal against air leakage during structural loads.

The film was used in a manner that did not influence the test results.

Drawings to be Submitted:

Submittal drawings numbered, 2037W sheets 1 thru 3 of 3, and marked with the terms a part of this report.

Page 8 of 8 Report #: Ingersoll Rand CTLA 2037W-1

Remarks:

Detailed drawings were available for laboratory records and comparison to the test specimen at the time of this report. A copy of this report along with representative sections of the test specimen will be retained by CTL for a period of ten (10) years. The results obtained apply only to the specimen tested.

This test report does not constitute certification of this product, but only that the above test results were obtained using the designated test methods and they indicate compliance with the performance requirements (paragraphs as listed) of the above referenced specifications.

Certified Testing Laboratories assumes that all information provided by the client is accurate and that the physical and chemical properties of the components are as stated by the manufacturer.

Observers

Yuriy Farber - Ingersoll-Rand Kevin Schmidt - Ingersoll-Rand Snehil Solanki - Ingersoll-Rand

Dade County Witness:

Not present

All Tests Witnessed by:

Ramesh Patel P.E. Stephen Gibbs

- CTL

Jonathan Pollange

Jonathan Pittenger
Lab Technician
Architectural Division
Certified Testing Laboratories

cc:

Ingersoll-Rand


(4)

Ramesh Patel

(1)

File

(1)



ERTHED ESTING ABORATORIES

