

ELEVATOR SOLUTIONS, INC.

3171 Rolling Hills Lane, Apopka, FL 32712
 Toll Free 866 501 6483 Office 407 889 8681 Fax 407 889 8673
 Email: sales@elevatorsolutions-fl.com

QUOTE **Savaria Orion Hydraulic LU/LA Elevator 2-Stop \$** **88,564.00**

Contractor

| | |
|-----------------------------------|---------------------------------|
| Company: Interstruct Orlando, LLC | Date: May 6, 2024 |
| Name: Clayton Sims | Office Phone: 407-912-1771 |
| Address: 814 W Church St | Cell: 321-355-9259 |
| City: Orlando | Email: csims@interstructinc.com |
| State: FL | Alt Contact: |
| Zipcode: 32805 | Alt Email: |

Job Site

Registered Owner

| | |
|------------------------------------|-----------------------------------|
| Project: Maxliving Headquarters | Owner: Nelson Irene |
| Address: 6404 Old Winter Garden Rd | Owner Address: |
| City: Orlando | Email: nelson.irene@maxliving.com |
| State: FL | Phone: 407-849-0025 |
| Zipcode: 32835 | County: Orange |

ELEVATOR SPECIFICATIONS

Standard Insurance Included -

Manufacturer & Model: Bonding, Umbrella, Waiver of Subrigations Are Additional to Quote
 Labor Limited Warranty: Savaria Orion Hydraulic LU/LA Elevator 2-Stop
 Manufacturers Limited Warranty: 1 Year From Completion Date
 Manufacturers Extended Limited Warranty: 1 Year From Ship Date
 Type of Complete Install: Available: Extended +2 Yr Parts Warranty with MCP Servicing - See Note C
Type 3

| | | | |
|------------------------|------------------------------------------------------------|----------------|------------------|
| Travel & Overhead | Travel: Up To 176" | Overhead: 134" | Pit Depth: 14" |
| Speed | Up To 30 FPM | | |
| Capacity | 1400 lbs | | |
| Wall Panel Finish | Arch White PS222W713 Steel Cab Flat Panel | | |
| Cab Size | 51"W x 51"D x 85 3/8"H | | |
| Ceiling Style & Finish | Flat Panel Standard White | | |
| Ceiling Lights | Stainless Steel #4 POT Lights | | |
| Handrail | Cylindrical Stainless Steel #4 | | |
| Cab Operator Panel | Standard Keyless Stainless Steel #4 | | |
| Communications | Hands Free Phone w Communication Pkg | | |
| Additional Options | Phase 1 Fire Service | | |
| Hall Call Stations | Keyless Stainless Steel #4 Call Only Push Button | | |
| Platform/Cab Doors | Auto Operated 2 Speed Doors in Architectural White Finish | | |
| Hoistway/Landing Doors | Auto Operated 2 Speed Sliding Doors in Primer Grey Finish | | |
| Flooring | Standard Plywood as Flooring Finishes to be Done by Others | | |
| Total Quote | \$ | | 88,564.00 |

- Notes:** Includes All Code Required Signage, Data Tags, Certificate Frame, Site Paperwork, & 1 Key Set
- Note A:** THIS QUOTED PRICE IS VALID IF UNIT IS ORDERED WITHIN 90 DAYS OF QUOTE DATE. ITEMS ORDERED AFTER THAT DATE WILL NEED TO BE CONFIRMED WITH MANUFACTURER. ALLOW 3 WEEKS FOR PLANS & ONCE APPROVED ALLOW 15 WEEKS FOR PRODUCTION & DELIVERY.
- Note B:** Please plan on additional time for jobs which may be delayed due to the worldwide supply chain of many elevator/lift components causing delays, shortages, or extended ETA's. Issues are present with all manufacturers and other sources for parts. To compensate for this challenge, please plan an additional 3 weeks for any possible issues run across during installation of your equipment and have all Items by Others, the shaft, power to job plus disconnects and any other electrical completed at least 6 weeks before job needs the Certificate of Occupancy.
- Note C:** 2 Additional Years From Ship Date (Total of 3 Years) Extended Parts Warranty (Labor Not Incuded) Available at \$3,240 Per Year - 1st Year To Be Paid Within 3 Months of Elevator Completion. Will Include Maintenance Control Program Compliance Servicing (Done Quarterly) with Extended Parts Warranty. Does Not Include Annual Inspections.
- Note D:** Measured Plans & Drawings Provided Plus 2 Revisions Included (More than 1 change per revision allowed; Additional Revisions Will Be a Change Order At \$350 Each) ; All Work Required to Comply with ASME A17.1.2019
- Note E: ITEMS TO BE DONE BY OTHERS:**
1. Hoistway must be plumb, square & meet plan specifications to within 1/8". Must provide structurally sound wall to handle imposed loads per planning guide requirements..
 2. Electrical disconnects must be provided as shown on plans & labeled on disconnect with: "Disconnect Breaker Box #__" and below that "Breaker #__". & License # on Disconnect. Label inside breaker box which is for elevator disconnect. Sign stating: "Danger - Parts of the controller are not de-energized by this switch".
 3. Location of electrical components as shown on plans.
 4. Telephone jack as shown on plans with dedicated, active & monitored phone line as required
 5. Provide fire/smoke alarm system as required
 6. GC to provide and install pit ladder & hoist beam
 7. Any additional electrical requirements per drawings/plans
 8. Finished flooring to be provided by others.
- Signature _____