



**MASONRY STRAP
INSTALLATION**




**FRAME JAMB SECTION (TYP)
HORIZONTAL SECTION**

MAXIMUM FRAME	DP	IMPACT
111 13/16 x 98 1/2	+35/-35	NO

1 1/2" MIN. EMBEDMENT
3/4" MINIMUM EDGE DISTANCE
1/4" MAX. SHIM SPACE



**FRAME SECTION (TYP)
VERTICAL SECTION**



TYPICAL ELEVATION WITH FASTENER SPACING

**MASONRY STRAP
INSTALLATION**

1 1/2" MIN. EMBEDMENT
3/4" MINIMUM EDGE DISTANCE
1/4" MAX. SHIM SPACE

MAXIMUM FRAME	DP	IMPACT
111 13/16 x 98 1/2	+35/-35	NO

1 1/2" MIN. EMBEDMENT
3/4" MINIMUM EDGE DISTANCE
1/4" MAX. SHIM SPACE

Installation Notes:

1. Seal flange/frame to substrate. Sill shall be set on a continuous serpentine bead of structural grade silicone caulk when no fastener is used to anchor the sill (typical).
2. Use 2 - #8 PFH or larger fasteners through masonry strap with sufficient length to penetrate a minimum of 1 1/2" into the buck. For 2x wood frame substrate (min. S.G. = 0.42).
3. Use 2 - #8 PFH or larger fasteners through masonry strap into jamb without penetrating through the jamb into product causing visibility or collateral damage to product.
4. Host structure (wood buck, masonry, steel) to be designed and anchored to properly transfer all loads to the structure and is the responsibility of the architect/engineer of record for the project of installation.
5. Use 5 - #8 PH or greater fastener thru the strike plate in the head with sufficient length to penetrate a minimum of 1 1/2" into the wood framing.

General Notes:

1. The product shown herein is designed, tested and manufactured to comply with the wind load criteria of the adopted International Building Code (IBC), the International Residential Code (IRC), the current Florida Building Code (FBC) and the Industry requirement for the stated conditions.
2. All glazing shall conform to ASTM E1300.
3. Use structural or composite shims where required.
4. Masonry strap specifications: 20 Ga. galvanized steel, .036" min. thickness x 1.5" min. width.

This schedule addresses only the fasteners required to anchor the unit to achieve the rated design pressure and impact performance. (Where applicable) up to the size limitations noted. It is not intended as a guide to the installation process and does not address the sealing consideration that may arise in different wall conditions. For the complete installation procedure, see the instructions packaged with the unit or go to www.jeld-wen.com.

DISCLAIMER:

This drawing and its contents are confidential and are not to be reproduced or copied in whole or in part or used or disclosed to others except as authorized by JELD-WEN Inc.

"AS TESTED"	
--------------------	--

DATE: 01/26/2022	DRAWN BY: J.HAWKINS	SCALE: NTS	TITLE: Custom Clad Inswing 3-Panel Door
CHECKED BY: G.GARDNER	APPROVED BY: D.STOKES	RECORD No.: D016241	
REPORT No.: NCTL-310-21-052 E1A0	CAD DWG. No.: CUSCLISW3PH Cert	REV: A	SHEET 1 OF 1

JELD-WEN 3737 LAKEPORT BLVD.
KLAMATH FALLS OR, 97601
PHONE: (800) 535-3936