## EVALUATION REPORT OF CENTRAL STATES MANUFACTURING, INC. '26 GA. HORIZON LOC PANEL'

## FLORIDA BUILDING CODE 7TH EDITION (2020) FLORIDA PRODUCT APPROVAL FL 14026.2-R5 ROOFING METAL ROOFING

Prepared For: Central States Manufacturing, Inc. 302 Jane Place Lowell, AR 72745 Telephone: (800) 356-2733 Fax: (800) 356-2971

Prepared By: Bala Sockalingam, Ph.D., P.E. Florida Professional Engineer #62240 1216 N Lansing Ave., Suite C Tulsa, OK 74106 Telephone: (918) 492-5992 FAX: (866) 366-1543

This report consists of Evaluation Report (3 Pages including cover) Installation Details (1 Page)



Report No. C2399-2 Date: 9.30.2020 Manufacturer: Central States Manufacturing, Inc.

Product Name: Horizon Loc Panel

Panel Description: Max. 16" wide coverage with 1" high ribs

- Materials: Minimum 26 ga., 50 ksi steel. Galvanized coated steel (ASTM A653) or Galvalume coated steel (ASTM A792) or painted steel (ASTM A755). Corrosion resistant as per FBC 2020 Section 1507.4.3.
- Deck Description: Min. 7/16" thick OSB or min. 15/32" thick APA rated plywood or min. <sup>3</sup>/<sub>4</sub>" thick wood plank (min SG of 0.42) for new and existing constructions. Designed by others and installed as per FBC 2020.
- Underlayment: Minimum underlayment as per FBC 2020 Section 1507.4.5.1. Required for new construction.
- Slope: 1/4:12 or greater in accordance with FBC 2020 Section 1507.4.2

Design Uplift Pressure: (Factor of Safety = 2)

- System 1:56.0 psf at seam fastener spacing of 6.5" o.c. along panel seam into<br/>min. 7/16" thick OSB or min. 15/32" thick plywood.
- System 2: 78.5 psf at seam fastener spacing of 4.75" o.c. along panel seam into min. 7/16" thick OSB or min. 15/32" thick plywood with and 3/8" diameter continuous bead of Weathermaster metal roof sealant applied in the male rib.
- System 3: 138.5 psf at seam fastener spaced at 4.75" o.c. along panel seam into min. 15/32" thick plywood deck with exterior fasteners spaced at 12" o.c. and 3/16" diameter continuous bead Novaflex silicone or Weathermaster metal roof sealant applied in the male rib.
- Seam Fastener: #10 x 1" wafer head wood screws along panel seam. Fastener shall be of sufficient length to penetrate through the deck a minimum of 1/4". Fasteners are corrosion resistant as per FBC 2020 Section 1507.4.4.
- Exterior Fastener: #10 x 1" long Kwikseal II Woodbinder screws with sealing washer or approved equal. Located on the panel flat at 1.25" from either side of panel sidelap. Spaced at maximum 12" o.c. along panel length. Fasteners are corrosion resistant as per FBC 2020 Section 1507.4.4.
- Test Standards: Roof assembly tested in accordance with UL580-06 'Uplift Resistance of Roof Assemblies' & UL1897-04 'Uplift Tests for Roof Covering Systems'.

Test Equivalency: The test procedures in UL 1897-04 comply with test procedures prescribed in UL 1897-12.

- Code Compliance: The product described herein has demonstrated compliance with FBC 2020 Section 1507.4.
- Product Limitations: Design wind loads shall be determined for each project in accordance with FBC 2020 Section 1609 or ASCE 7-16 using allowable stress design. The maximum fastener spacing listed herein shall not be exceeded. This product is not approved for use in the High Velocity Hurricane Zone. Fire classification is not within scope of this Evaluation Report. Refer to FBC 2020 Section 1505 and current approved roofing materials directory or ASTM E108/UL790 report from an accredited laboratory for fire ratings of this product.
- Supporting Documents: UL580 & UL1897 Test Reports Force Engineering and Testing Inc. Report No. 410-0022T-13, Reporting Date 12/6/2013

Farabaugh Engineering and Testing Inc. Project No. T286-15, Reporting Date 10/20/15 Project No. T245-17, Reporting Date 9/1/17

