




Dunbarton
CORPORATION

868 MURRAY ROAD, DOTHAN, AL 36303


**"REDIFLEX"
TWO-PIECE STEEL FRAME SYSTEM
UTILIZING A
MASONITE OPAQUE STEEL DOOR PANEL
"IMPACT"**

GENERAL NOTES

1. This product has been evaluated and is in compliance with the 7th Edition (2020) Florida Building Code (FBC) structural requirements excluding the "High Velocity Hurricane Zone" (HVHZ).
2. Product anchors shall be as listed and spaced as shown on details. Anchor embedment to base material shall be beyond wall dressing or stucco.
3. When used in areas requiring wind borne debris protection this product complies with FBC Sections 1609.1.2 & R301.2.1.2 and does not require an impact resistant covering. This product meets missile level "D" and includes Wind Zone 4 as defined in ASTM E 1996 and FBC Sections 1609.1.2.2 & R301.2.1.2.1.
4. For 2x stud framing construction, anchoring of these units shall be the same as that shown for 2x buck masonry construction.
5. Site conditions that deviate from the details of this drawing require further engineering analysis by a licensed engineer or registered architect.




REDIFLEX TWO-PIECE



INSWING / OUTSWING

TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	Typical elevation, design pressures & general notes
2	Steel frame cross sections & details
3	Door panel details
4	Horizontal cross sections
5	Vertical cross sections
6	Buck & frame anchoring - masonry 2x buck
7	Buck & frame anchoring - steel/2x stud
8	Bill of materials and components







OVERALL FRAME DIMENSION	DESIGN PRESSURE (PSF)	
	POSITIVE	NEGATIVE
39.5" X 85.5"	+ 66.0	- 66.0



August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409
 R.W.
 BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813


PRODUCT:	DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME	
PART OR ASSEMBLY:	TYPICAL ELEVATIONS, DESIGN PRESSURES & GENERAL NOTES	
NO.	DATE	REVISIONS
4	8/11/20	UPDATE TO 7TH ED. (2020) FBC DAC
3	9/30/17	UPDATE TO 6TH ED. (2017) FBC
2	1/27/16	REVISE ANCHORING LFS
1	3/23/15	UPDATE TO 5TH ED. (2014) FBC JK
NO.	DATE	BY
DATE: 03/14/12		
SCALE: N.T.S.		
DWG. BY: JK		
CHK. BY: LFS		
DRAWING NO.: FL-15341.2		
SHEET 1 OF 8		

\\dc01\nwbc\Clients\Dunbarton Permanent\A - Florida Product Approvals\FL-15341 - Exterior Door Components - Rediflex Steel Frames\C - Drawings\FL-15341 (2020)\FL-15341.1-4.dwg



NOTES:

1. HEADER AND SIDE BASE JAMB (41) MINIMUM 18 GA. GALV. STEEL.
2. HEADER AND SIDE CLOSURE JAMB (42) MINIMUM 22 GA. GALV. STEEL.
3. FRAME SHOWN WITHOUT OPTIONAL STEEL TRIM CASING.
4. NON-KERF FRAMES DO NOT MEET AIR AND WATER CRITERIA.



August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409





PRODUCT:
 DUNBARTON REDIFLEX
 TWO-PIECE STEEL FRAME

PART OR ASSEMBLY:
 STEEL FRAME CROSS SECTIONS
 & DETAILS

NO.	DATE	REVISIONS
4	8/11/20	UPDATE TO 7TH ED. (2020) FBC DAC
3	9/30/17	UPDATE TO 6TH ED. (2017) FBC LFS
2	1/27/16	REVISE ANCHORING LFS
1	3/23/15	UPDATE TO 5TH ED. (2014) FBC JK
		BY

DATE: 03/14/12
 SCALE: N.T.S.
 DWG. BY: JK
 CHK. BY: LFS
 DRAWING NO.:
 FL-15341.2
 SHEET 2 OF 8

R.W. BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813





August 11, 2020
 Documents Prepared By: Lyndon F. Schmidt
 P.E. No. 43409


STATE OF FLORIDA
REGISTERED PROFESSIONAL ENGINEER
 L. F. SCHMIDT
 LICENSE No. 43409

R.W. BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813


PRODUCT:		DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME	
PART OR ASSEMBLY:		DOOR PANEL DETAILS	
NO.	DATE	BY	REVISIONS
4	8/11/20	DAC	UPDATE TO 7TH ED. (2020) FBC
3	9/30/17	LFS	UPDATE TO 6TH ED. (2017) FBC
2	1/27/16	LFS	REVISE ANCHORING
1	3/23/15	JK	UPDATE TO 5TH ED. (2014) FBC




2
4 **HORIZONTAL CROSS SECTION**
Optional steel stud construction




4
4 **HORIZONTAL CROSS SECTION**
Optional steel stud construction



5
4 **HORIZONTAL CROSS SECTION**
Optional 2X Stud Construction




1
4 **HORIZONTAL CROSS SECTION**
2X wood buck




3
4 **HORIZONTAL CROSS SECTION**
2X wood buck

Note:
1. A minimum of three threads must protrude completely through the supporting steel stud.




August 11, 2020
Documents Prepared By:
Lyndon F. Schmidt
P.E. No. 43409
RW
BUILDING CONSULTANTS, INC.
P.O. Box 230, Valrico, FL 33595
Phone No.: 813.659.9197
FBPE Registry No. 9813


PRODUCT:		DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME	
PART OR ASSEMBLY:		HORIZONTAL CROSS SECTIONS	
NO.	DATE	BY	REVISIONS
4	8/11/20	DAC	UPDATE TO 7TH ED. (2020) FBC
3	9/30/17	LFS	UPDATE TO 6TH ED. (2017) FBC
2	1/27/16	LFS	REVISE ANCHORING
1	3/23/15	JK	UPDATE TO 5TH ED. (2014) FBC
DATE: 03/14/12			
SCALE: N.T.S.			
DWG. BY: JK			
CHK. BY: LFS			
DRAWING NO.: FL-15341.2			
SHEET 4 OF 8			




1 VERTICAL CROSS SECTION
5 2X wood buck




2 VERTICAL CROSS SECTION
5 Optional steel stud construction



3 VERTICAL CROSS SECTION
5



4 VERTICAL CROSS SECTION
5 Shown w/ ADA threshold




5 VERTICAL CROSS SECTION
5


August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409

RW
 BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813

PRODUCT:		DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME			
PART OR ASSEMBLY:		VERTICAL CROSS SECTIONS			
NO.	DATE	BY	REVISIONS		
4	8/11/20	DAC	UPDATE TO 7TH ED. (2020) FBC		
3	9/30/17	LFS	UPDATE TO 6TH ED. (2017) FBC		
2	1/27/16	LFS	REVISE ANCHORING		
1	3/23/15	JK	UPDATE TO 5TH ED. (2014) FBC		
DATE:		03/14/12			
SCALE:		N.T.S.			
DWG. BY:		JK			
CHK. BY:		LFS			
DRAWING NO.:		FL-15341.2			
SHEET		5 OF 8			




BUCK ANCHORING
Masonry




FRAME ANCHORING
Masonry construction


R ITEM #R IS USED ONLY WHEN ITEM #71, THE ADA THRESHOLD IS USED




STRIKE JAMB



HINGE JAMB



STRIKE PLATE DETAIL



HINGE DETAIL 1


CONCRETE ANCHOR NOTES:

- Concrete anchor locations at the corners may be adjusted to maintain the min. edge distance to mortar joints.
- Concrete anchor locations noted as "MAX. ON CENTER" must be adjusted to maintain the min. edge distance to mortar joints, additional concrete anchors may be required to ensure the "MAX. ON CENTER" dimension are not exceeded.
- Concrete anchor table:

ANCHOR TYPE	ANCHOR SIZE	MIN. EMBEDMENT	MIN. CLEARANCE TO MASONRY EDGE	MIN. CLEARANCE TO ADJACENT ANCHOR
ITW TAPCON®	1/4"	1-1/4"	2"	4"
DeWALT ULTRACON+®	1/4"	1-1/4"	1"	4"


WOOD SCREW INSTALLATION NOTES:

- Maintain a minimum 5/8" edge distance, 1" end distance, & 1" o.c. spacing of wood screws to prevent the splitting of wood.




August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409
 R.W. BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813

PRODUCT:		DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME	
PART OR ASSEMBLY:		BUCK AND FRAME ANCHORING MASONRY 2X BUCK	
	DAC	FBC	FBC
	LFS	FBC	FBC
	LFS	JK	BY
	JK	FBC	
	BY		
	NO.	DATE	REVISIONS
4	8/11/20	UPDATE TO 7TH ED. (2020)	FBC
3	9/30/17	UPDATE TO 6TH ED. (2017)	FBC
2	1/27/16	REVISE ANCHORING	
1	3/23/15	UPDATE TO 5TH ED. (2014)	FBC
DATE:		03/14/12	
SCALE:		N.T.S.	
DWG. BY:		JK	
CHK. BY:		LFS	
DRAWING NO.:		FL-15341.2	
SHEET		6 OF 8	




BUCK ANCHORING
Steel stud




FRAME ANCHORING
Stud construction


R ITEM #R IS USED ONLY WHEN ITEM #71, THE ADA THRESHOLD IS USED




STRIKE JAMB



HINGE JAMB



STRIKE PLATE DETAIL



HINGE DETAIL 1


CONCRETE ANCHOR NOTES:

- Concrete anchor locations at the corners may be adjusted to maintain the min. edge distance to mortar joints.
- Concrete anchor locations noted as "MAX. ON CENTER" must be adjusted to maintain the min. edge distance to mortar joints, additional concrete anchors may be required to ensure the "MAX. ON CENTER" dimension are not exceeded.
- Concrete anchor table:

ANCHOR TYPE	ANCHOR SIZE	MIN. EMBEDMENT	MIN. CLEARANCE TO MASONRY EDGE	MIN. CLEARANCE TO ADJACENT ANCHOR
ITW TAPCON®	1/4"	1-1/4"	2"	4" / 3" (steel stud)
DeWALT ULTRACON®	1/4"	1-1/4"	1"	4"

WOOD SCREW INSTALLATION NOTES:






- Maintain a minimum 5/8" edge distance, 1" end distance, & 1" o.c. spacing of wood screws to prevent the splitting of wood.



August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409
 R.W. BUILDING CONSULTANTS, INC.
 P.O. Box 230, Vairico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813

PRODUCT:		DUNBARTON REDIFLEX TWO-PIECE STEEL FRAME	
PART OR ASSEMBLY:		BUCK & FRAME ANCHORING STEEL/2X STUD	
		DAC	LFS
4	8/11/20	UPDATE TO 7TH ED. (2020)	FBC
3	9/30/17	UPDATE TO 6TH ED. (2017)	FBC
2	1/27/16	REVISE ANCHORING	LFS
1	3/23/15	UPDATE TO 5TH ED. (2014)	FBC
	NO.	DATE	BY
			REVISIONS
DATE:		03/14/12	
SCALE:		N.T.S.	
DWG. BY:		JK	
CHK. BY:		LFS	
DRAWING NO.:		FL-15341.2	
SHEET		7 OF 8	

BILL OF MATERIALS		
ITEM	DESCRIPTION	MATERIAL
B	2X BUCK SG >= 0.55	WOOD
E	MASONRY - 3,000 PSI MIN. CONCRETE CONFORMING TO ACI 301 OR HOLLOW BLOCK CONFORMING TO ASTM C90 OR ASTM A653 STEEL	CONCRETE
P	1/4" X 2-3/4" DeWALT OR ITW PFH CONCRETE SCREW	STEEL
R	1/4" X 1-3/4" ITW PFH CONCRETE SCREW	STEEL
13	#10 X 3/4" HILTI KWIK-FLEX SELF-DRILLING SCREW	STEEL
15	1/4" X 1-3/4" ITW HWH CONCRETE SCREW	STEEL
17	SSMA STUD 550S162-54 (Fy = 33 ksi, Fu = 45 ksi)	STEEL
19	#8 x 3/8" PFH MACHINE SCREW	STEEL
20	10-24 X 1/2" FLAT HEAD SCREW	STEEL
21	#9 X 1.0" PFH WOOD SCREW	STEEL
22	4" X 4" BUTT HINGE	STEEL
23	#6 X 1-1/4" PFH WOOD SCREW (1-1/8" MIN. EMBEDMENT)	STEEL
29	JAMB HINGE REIN. 14 GA. 4" x 4" x 1.53" (.075" GALV. STEEL) BY DUNBARTON FRO0505	STEEL
30	COMPRESSION WEATHERSTRIPPING QLON QDS 650 BY SCHLEGEL	FOAM
36	DOOR BOTTOM SWEEP by DUNBARTON	PVC
41	REDIFLEX JAMB BASE 18 GA. (.042" MIN. GALV. STEEL) BY DUNBARTON	STEEL
42	REDIFLEX JAMB CLOSURE 22 GA. (.026" MIN. GALV. STEEL) BY DUNBARTON	STEEL
43	DOOR PANEL .020" THK. GALV. STEEL, WOOD EDGE BY MASONITE	STEEL
44	WOOD LOCK STILE 1.708" x .970" BY MASONITE	WOOD
45	WOOD LOCK BLOCK 1.708" x 3.375" x 10.75" F. J. PINE BY MASONITE	WOOD
46	WOOD TOP RAIL 1.708" x .908" BY MASONITE	WOOD
47	WOOD BOTTOM RAIL 1.708" x 1.010" BY MASONITE	WOOD
50	STEEL DOOR PANEL - BY MASONITE	STEEL
51	SIDE STILE 0.043" ROLL FORMED STEEL BY MASONITE	STEEL
52	DOOR PANEL 0.020" THK. GALV. STEEL, STEEL EDGE BY MASONITE	STEEL
53	WOOD LOCK REIN. FINGER JOINTED PINE BY MASONITE	WOOD
54	POLYURETHANE FOAM CORE	POLYURETHANE
55	BOTTOM RAIL .032" THK. ROLL FORMED STEEL BY MASONITE	STEEL
56	TOP RAIL .043" THK ROLL FORMED STEEL BY MASONITE	STEEL
57	PLASTIC LOCK RING	PLASTIC
58	STRIKE PLATE - DEADBOLT	STEEL
59	STRIKE PLATE - LATCHBOLT	STEEL
60	EVERSEF LATCH w/ EVERSEF DEADBOLT	STEEL
61	KWIKSET SERIES LATCH w/ KWIKSET SERIES (660) DEADBOLT	STEEL
62	SCHLAGE LATCH (F SERIES) w/ SCHLAGE DEADBOLT (B60/62)	STEEL
70	OUTSWING BUMP THRESHOLD by ENDURA	ALUM
71	ADA THRESHOLD by ENDURA	ALUM
72	INSWING FIXED THRESHOLD BY ENDURA	ALUM
73	2X FRAMING: SG >= 0.42	WOOD
74	#8 x 1-3/4" PFH SMS (1-1/8" MIN. EMBEDMENT)	STEEL



August 11, 2020
 Documents Prepared By:
 Lyndon F. Schmidt
 P.E. No. 43409

RW BUILDING CONSULTANTS, INC.
 P.O. Box 230, Valrico, FL 33595
 Phone No.: 813.659.9197
 FBPE Registry No. 9813

PRODUCT:
 DUNBARTON REDIFLEX
 TWO-PIECE STEEL FRAME

PART OR ASSEMBLY:
 BILL OF MATERIALS
 & COMPONENTS

NO.	DATE	REVISIONS
4	8/11/20	UPDATE TO 7TH ED. (2020) FBC DAC
3	9/30/17	UPDATE TO 6TH ED. (2017) FBC LFS
2	1/27/16	REVISE ANCHORING LFS
1	3/23/15	UPDATE TO 5TH ED. (2014) FBC JK
		BY

DATE: 03/14/12
 SCALE: N.T.S.
 DWG. BY: JK
 CHK. BY: LFS
 DRAWING NO.: FL-15341.2
 SHEET 8 OF 8