

INSTALLATION NOTES:

- ONE (1) INSTALLATION ANCHOR IS REQUIRED AT EACH ANCHOR LOCATION SHOWN.
- THE NUMBER OF INSTALLATION ANCHORS DEPICTED IS THE MINIMUM NUMBER OF ANCHORS TO BE USED FOR PRODUCT INSTALLATION.
- INSTALL INDIVIDUAL INSTALLATION ANCHORS WITHIN A TOLERANCE OF ±1/2 INCH OF THE DEPICTED LOCATION IN THE ANCHOR LAYOUT DETAIL (I.E., WITHOUT CONSIDERATION OF TOLERANCES). TOLERANCES ARE NOT CUMULATIVE FROM ONE INSTALLATION ANCHOR TO THE NEXT.
- SHIM AS REQUIRED AT EACH INSTALLATION ANCHOR WITH LOAD BEARING SHIM(S). MAXIMUM ALLOWABLE SHIM STACK TO BE 1/4 INCH. SHIM WHERE SPACE OF 1/16 INCH OR GREATER OCCURS. SHIM(S) SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER.
- FOR INSTALLATION INTO WOOD FRAMING USE #14 WOOD SCREWS OF SUFFICIENT LENGTH TO ACHIEVE 1-1/2 INCH MINIMUM EMBEDMENT INTO WOOD SUBSTRATE.
- FOR INSTALLATION THROUGH 1X BUCK TO CONCRETE/MASONRY, OR DIRECTLY INTO CONCRETE/MASONRY, USE 1/4 INCH DIAMETER ITW TAPCONS OF SUFFICIENT LENGTH TO ACHIEVE 1-1/4 INCH MINIMUM EMBEDMENT.
- MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE WALL FINISHES, INCLUDING BUT NOT LIMITED TO STUCCO, FOAM, BRICK VENEER, AND SIDING.
- INSTALLATION ANCHORS, ALUMINUM FRAMING, AND ASSOCIATED HARDWARE MUST BE MADE OF CORROSION RESISTANT MATERIAL OR HAVE A CORROSION RESISTANT COATING IN ACCORDANCE WITH FBC PROTECTION STANDARDS.
- FOR GROUT FILLED BLOCK, DO NOT INSTALL INSTALLATION ANCHORS INTO MORTAR JOINTS. EDGE DISTANCE IS MEASURED FROM FREE EDGE OF BLOCK OR EDGE OF MORTAR JOINT INTO FACE SHELL OF BLOCK.
- INSTALLATION ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM STRENGTH SPECIFIED BY THE ANCHOR MANUFACTURER.
- INSTALLATION ANCHOR CAPACITIES FOR PRODUCTS HEREIN ARE BASED ON SUBSTRATE MATERIALS WITH THE FOLLOWING PROPERTIES:
 - WOOD - MINIMUM SPECIFIC GRAVITY OF 0.55.
 - CONCRETE - MINIMUM COMPRESSIVE STRENGTH OF 3152 PSI.
 - MASONRY - STRENGTH CONFORMANCE TO ASTM C-90, (OR GREATER). MINIMUM COMPRESSIVE STRENGTH OF 2000 PSI.

GENERAL NOTES:

- THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE CURRENT FLORIDA BUILDING CODE (FBC), INCLUDING HVHZ AND HAS BEEN EVALUATED ACCORDING TO THE FOLLOWING:
 - TAS 201-94
 - TAS 202-94
 - TAS 203-94
- ADEQUACY OF THE EXISTING STRUCTURAL CONCRETE/MASONRY AND 2X FRAMING AS A MAIN WIND FORCE RESISTING SYSTEM CAPABLE OF WITHSTANDING AND TRANSFERRING APPLIED PRODUCT LOADS TO THE FOUNDATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- 1X AND 2X BUCKS (WHEN USED) SHALL BE DESIGNED AND ANCHORED TO PROPERLY TRANSFER ALL LOADS TO THE STRUCTURE. BUCK DESIGN AND INSTALLATION IS THE RESPONSIBILITY OF THE ENGINEER OR ARCHITECT OF RECORD FOR THE PROJECT OF INSTALLATION.
- THE INSTALLATION DETAILS DESCRIBED HEREIN ARE GENERIC AND MAY NOT REFLECT ACTUAL CONDITIONS FOR A SPECIFIC SITE. IF SITE CONDITIONS CAUSE INSTALLATION TO DEVIATE FROM THE REQUIREMENTS DETAILED HEREIN, A LICENSED ENGINEER OR ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE WITH THIS DOCUMENT IN NON-HVHZ AREAS AND TO BE REVIEWED BY A.H.J (AUTHORITY HAVING JURISDICTION).
- DEVIATION FROM THIS APPROVAL WITHIN THE HVHZ REQUIRES ONE-TIME APPROVAL FROM MIAMI-DADE COUNTY (PERA).
- APPROVED IMPACT PROTECTIVE SYSTEM **IS NOT REQUIRED** ON THIS PRODUCT IN AREAS REQUIRING IMPACT RESISTANCE.
- WINDOW FRAME MATERIAL: WOOD AURALAST
CLADDING MATERIAL: ALUMINUM 6063-T5
- IN ACCORDANCE WITH CURRENT FBC, DISSIMILAR METALS INCLUDING FASTENERS THAT MAY COME INTO CONTACT WITH ALUMINUM UNIT FRAME SHALL BE PROTECTED AS DEFINED IN SEC 2003.
- IN ACCORDANCE WITH CURRENT FBC, SECTION 2411 WOOD COMPONENTS SHALL HAVE BEEN PRESERVATIVE TREATED OR SHALL BE OF A DURABLE SPECIES AS DEFINED IN SECTION 2326.
- GLASS MEETS THE REQUIREMENTS OF ASTM E 1300-04 GLASS CHARTS. SEE SHEET 4 FOR GLAZING DETAILS.

JELD-WEN, inc.

CUSTOM COLLECTION ALUMINUM CLAD DIRECT SET WINDOW

TABLE OF CONTENTS		
SHEET	REVISION	SHEET DESCRIPTION
1	-	INSTALLATION & GENERAL NOTES
2	-	ELEVATION & QUALIFIED SHAPES
3	-	ELEVATIONS & ANCHOR LAYOUTS
4	-	DESIGN SCHEDULE & GLAZING DETAILS
5	-	ASSEMBLY SECTIONS
6	-	NAIL FIN INSTALLATION DETAILS
7	-	THROUGH FRAME INSTALLATION DETAILS
8	-	STRAP INSTALLATION DETAILS
9	-	COMPONENTS & BILL OF MATERIALS

3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

JELD-WEN

DATE: 3/30/2012

SCALE: NTS

TITLE:

PROJECT ENGINEER:
--

DRAWN BY:
D. Vezo

CHECKED BY:

APPROVED BY:
--

PART/PROJECT No.:

IDENTIFIER No.
N/A

PLANT NAME AND LOCATION:
Bend, Oregon














CAD DWG. No.:
JW031

REV: 00

SHEET 1 OF 9

Custom Clad Direct Set Window
Installation & General Notes


QUALIFIED SHAPED UNITS




SHAPED UNITS NOTES


1. UNITS OF ANY SHAPE ARE ALLOWED PROVIDED CONSTRUCTION, GLAZING, & ANCHORAGE ARE PER DETAILS SHOWN HEREIN.
2. ALL SHAPED UNITS SHALL FIT WITHIN THE RECTANGULAR AREA SHOWN IN DESIGN SCHEDULE.

JELD-WEN		3737 Lakeport Blvd Klamath Falls, OR. 97601 Phone: (541) 882-3451	
PROJECT ENGINEER: --	DATE: 3/30/2012	SCALE: NTS	TITLE:
DRAWN BY: D. Vezo			
CHECKED BY:			
APPROVED BY:			
PART/PROJECT No.:			
IDENTIFIER No.:			
PLANT NAME AND LOCATION: Bend, Oregon		CAD DWG. No.: JW031	REV: 00 SHEET 2 OF 9
Custom Clad Direct Set Window Elevation & Qualified Shapes			






1
3 ANCHOR ELEVATION FOR
INSTALLATION WITH NAIL FIN
N.T.S. EXTERIOR ELEV



2
3 ANCHOR ELEVATION FOR
INSTALLATION THROUGH FRAME
N.T.S. EXTERIOR ELEV



3
3 ANCHOR ELEVATION FOR
INSTALLATION WITH STRAP
N.T.S. EXTERIOR ELEV

ANCHOR SCHEDULE

TO HOLLOW BLOCK OR 3192 PSI MIN
CONCRETE HOST STRUCTURE

1/4" TAPCONS (ITW) THRU 1X OR
DIRECTLY INTO
MASONRY/CONCRETE WITH 1-1/4" MIN.
EMBEDMENT.

TO WOOD BUCK OR HOST STRUCTURE
(MIN S.G. = 0.55)

#14 WOOD SCREWS WITH 1-1/2" MIN.
THREAD PENETRATION.

ANCHOR NOTES

1. SEE ANCHOR ELEVATIONS FOR ANCHOR LOCATIONS AND/OR SPACING.
2. ANCHORAGE METHODS, INCLUDING ANCHOR TYPES SHOW MAXIMUM SPACING, ARE APPLICABLE TO ALL SHAPED UNIT SHOWN ON SHEET 2.
3. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.
4. TAPCONS MANUFACTURED BY ITW.
5. ENSURE MINIMUM 2-1/2" EDGE DISTANCE FOR ALL ANCHORS INTO CONCRETE AND INTO HOLLOW BLOCK.
6. WHERE ANCHORS FASTEN TO NARROW FACE OF STUD FRAMING, ANCHOR SHALL BE LOCATED IN CENTER OF NOMINAL 2X (MIN) WOOD STUD (i.e. 3/4" EDGE DISTANCE IS ACCEPTABLE FOR ANCHORS TO WOOD FRAMING).
7. WOOD HOST STRUCTURE SHALL BE "SOUTHERN PINES G=0.55 OR GREATER DENSITY.
8. MINIMUM EMBEDMENT SHALL BE AS NOTED IN ANCHOR SCHEDULE. MINIMUM EMBEDMENT AND EDGE DISTANCE EXCLUDE STUCCO, FOAM, BRICK, AND OTHER WALL FINISHES.
9. ANCHOR SCHEDULE APPLIES TO ALL PRODUCTS CERTIFIED HEREIN.
10. WHERE EXISTING STRUCTURE IS WOOD FRAMING, EXISTING CONDITIONS MAY VARY. FIELD VERIFY THAT FASTENERS ARE INTO ADEQUATE WOOD FRAMING MEMBERS, NOT INTO PLYWOOD.
11. WOOD BUCKS (BY OTHERS) SHALL BE ANCHORED PROPERLY TO TRANSFER LOADS TO THE EXISTING STRUCTURE.

JELD-WEN

3737 Lakeport Blvd
Klamath Falls, OR, 97601
Phone: (541) 882-3451

Custom Clad Direct Set Window
Elevations and Anchor Layouts

DATE: 3/30/2012

PROJECT ENGINEER: --

SCALE: NTS

DRAWN BY: D. Vezo

TITLE:

CHECKED BY: --

APPROVED BY: --

PART/PROJECT No.:


IDENTIFIER No. N/A

PLANT NAME AND LOCATION:
Bend, Oregon

CAD DWG. No.: JW031

REV: 00

SHEET 3 OF 9



DESIGN SCHEDULE

FRAME DIMENSION 'A'	DLO ALONG 'A'	18"	20"	24"	28"	30"	32"	40"	42"	48"	54"	60"	72"	84"	90"	96"	102"	108"	114"	120"	FRAME DIMENSION 'B'	
		14 1/4"	16 1/4"	20 1/4"	24 1/4"	26 1/4"	28 1/4"	36 1/4"	38 1/4"	44 1/4"	50 1/4"	56 1/4"	68 1/4"	80 1/4"	86 1/4"	92 1/4"	98 1/4"	104 1/4"	110 1/4"	116 1/4"	DLO ALONG 'B'	
18"	14 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	MAX. ALLOWABLE DESIGN PRESSURE (PSF)
20"	16 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
24"	20 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
28"	24 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
30"	26 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
32"	28 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
36"	32 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
40"	36 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
42"	38 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
48"	44 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	
54"	50 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	
56"	52 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	
60"	56 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	+80/-80	
64"	60 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
66"	62 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
72"	68 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
78"	74 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
84"	80 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
90"	86 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
96"	92 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
102"	98 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
108"	104 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
114"	110 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	
120"	116 1/4"	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+100/-100	+80/-80	+80/-80	---	---	---	---	---	---	---	---	

3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

JELD-WEN

Custom Clad Direct Set Window
Design Schedule and Glazing Details


DATE: 3/30/2012
SCALE: NTS
TITLE:

PROJECT ENGINEER: --
DRAWN BY: D. Vezo
CHECKED BY: --
APPROVED BY: --
PART/PROJECT No.: --

PLANT NAME AND LOCATION:
Bend, Oregon
CAD DWG. No.: JW031
REV: 00
SHEET 4 OF 9


GLAZING TYPE A

9/16" LAMINATED, LMI




GLAZING TYPE B

1 5/32" INSULATED LAMINATED, LMI




1 4 GLAZING DETAILS


N.T.S. VERTICAL SECTION



A
5 N.T.S. VERTICAL SECTION
TYPICAL HEAD ASSEMBLY



B
5 N.T.S. VERTICAL SECTION
TYPICAL SILL ASSEMBLY



C
5 N.T.S. HORIZONTAL SECTION
TYPICAL JAMB ASSEMBLY

D
5 N.T.S. HORIZONTAL SECTION
TYPICAL JAMB ASSEMBLY

JELD-WEN
3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

Custom Clad Direct Set Window
Assembly Sections

DATE: 3/30/2012
SCALE: NTS
TITLE:

PROJECT ENGINEER: --
DRAWN BY: D. Vezo
CHECKED BY: --
APPROVED BY: --
PART/PROJECT No.: --
IDENTIFIER No.: N/A

PLANT NAME AND LOCATION:
Bend, Oregon


CAD DWG. No.: JW031
REV: 00
SHEET 5 OF 9

INSTALLATION WITH FIN AT FRAME HEAD

A
6

N.T.S.

VERTICAL SECTION




INSTALLATION WITH FIN AT FRAME JAMB

D
6

N.T.S.

HORIZONTAL SECTION




INSTALLATION WITH FIN AT FRAME JAMB

C
6

N.T.S.

HORIZONTAL SECTION



NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.

NOTE: NAIL FIN INSTALLATION REQUIRES MINIMUM 2X GREATER PRESSURE TREATED WOOD BUCK (BY OTHERS) IN CONCRETE AND MASONRY HOST STRUCTURE.

INSTALLATION WITH FIN AT FRAME SILL

B
6

N.T.S.

VERTICAL SECTION

3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

JELD-WEN

Custom Clad Direct Set Window
Nail Fin Installation Details

DATE: 3/30/2012

SCALE: NTS

TITLE:

PROJECT ENGINEER:

DRAWN BY: D. Vezo

CHECKED BY:

APPROVED BY:

PART/PROJECT No.:


IDENTIFIER No. N/A

PLANT NAME AND LOCATION:
Bend, Oregon

CAD DWG. No.: JW031



REV: 00

SHEET 6 OF 9



INSTALLATION THROUGH FRAME HEAD

A
7 N.T.S. VERTICAL SECTION




INSTALLATION THROUGH FRAME SILL

B
7 N.T.S. VERTICAL SECTION

INSTALLATION THROUGH FRAME JAMB

D
7 N.T.S. HORIZONTAL SECTION



INSTALLATION THROUGH FRAME JAMB

C
7 N.T.S. HORIZONTAL SECTION

NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.

3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

JELD-WEN



Custom Clad Direct Set Window
Through Frame Installation Details

DATE: 3/30/2012	SCALE: NTS	TITLE:
PROJECT ENGINEER:	DRAWN BY: D. Vezo	CHECKED BY:
APPROVED BY:	PART/PROJECT No.:	IDENTIFIER No. N/A
CAD DWG. No.: JW031	REV: 00	SHEET 7 OF 9

PLANT NAME AND LOCATION:
Bend, Oregon

INSTALLATION WITH STRAP AT FRAME HEAD

A
8 N.T.S. VERTICAL SECTION




INSTALLATION WITH STRAP AT FRAME SILL

B
8 N.T.S. VERTICAL SECTION

INSTALLATION WITH STRAP AT FRAME JAMB

D
8 N.T.S. HORIZONTAL SECTION



INSTALLATION WITH STRAP AT FRAME JAMB

C
8 N.T.S. HORIZONTAL SECTION

NOTE: SEE ANCHOR SCHEDULE AND ANCHOR NOTES FOR REQUIRED EDGE DISTANCES AND EMBEDMENTS.

3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

JELD-WEN

Custom Clad Direct Set Window
Strap Installation Details

DATE: 3/30/2012

SCALE: NTS

TITLE:

PROJECT ENGINEER:

DRAWN BY: D. Vezo

CHECKED BY:

APPROVED BY:

PART/PROJECT No.:


IDENTIFIER No. N/A

PLANT NAME AND LOCATION:
Bend, Oregon

CAD DWG. No.: JW031

REV: 00






SHEET 8 OF 9



BILL OF MATERIALS

ITEM NO.	DESCRIPTION	PART NUMBER	MATERIAL	MANUFACTURER
1	FRAME CLADDING	VH-53639	ALUMINUM	INDALEX
2	JAMB	CA0176SJ	WOOD	
3	SASH STOP	CA0284SP	WOOD	
4	JAMB EXTENDER	CA260AJE	WOOD	
5	13 GA. INSTALL STRAP		STEEL	13 GA.
6	SILICONE SEALANT		SEALANT	DOW CORNING 899

NOTE: ALL WOOD COMPONENTS ARE PRESSURE TREATED AURALAST.



3737 Lakeport Blvd
Klamath Falls, OR. 97601
Phone: (541) 882-3451

Custom Clad Direct Set Window
Components and Bill of Materials

PROJECT ENGINEER: --

DRAWN BY: D. Vezo

CHECKED BY: --

APPROVED BY: --

PART/PROJECT No.: --

IDENTIFIER No.: N/A

DATE: 3/30/2012

SCALE: NTS

TITLE: --

CAD DWG. No.: JW031

REV: 00

SHEET 9 OF 9

PLANT NAME AND LOCATION:
Bend, Oregon