




1 COCHRANE AVE. PENNSBORO, WV 26415 PH.
800-426-2249

07-09 / 07-10 / 07-20
STORMBREAKER PLUS 300VL
IMPACT RESISTANT VINYL
HORIZONTAL 3-LITE SLIDING WINDOW
EQUAL LITE

REV. #:	REVISIONS:	REVISED BY:	DATE:

GENERAL NOTES:

1. THIS WINDOW SYSTEM IS DESIGNED TO COMPLY WITH THE 2014 FLORIDA BUILDING CODE, INCLUDING HVHZ, AND WAS TESTED USING METHODS TAS 201, TAS 202, AND TAS 203.
2. HIGH QUALITY CAULK SHALL BE USED AROUND THE ENTIRE WINDOW PERIMETER, INSIDE AND OUT. EXTERIOR CAULKING SHALL BE CAP BEAD FOR EQUAL LEG FRAMES, OR BEHIND FINS/FLANGES FOR THOSE FRAME TYPES.
3. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING WINDOW OPENING AND ALL WOOD FRAMING AROUND THE WINDOW.
4. WOOD BUCKS, BY OTHERS, MUST SUSTAIN ALL IMPOSED LOADS AND MUST BE PROPERLY ANCHORED TO TRANSFER LOADS TO THE STRUCTURE AND SHALL BE INSPECTED BY A BUILDING OFFICIAL. WOOD BUCK MIN. G = 0.42.
5. FOR INSTALLATION INTO CONCRETE/MASONRY, ANCHORS MUST NOT BE INSTALLED INTO MORTAR JOINTS. LOCATION SHOULD BE ADJUSTED SO THAT THE ANCHOR IS AT LEAST 2" FROM MORTAR JOINTS. CONCRETE/MASONRY SUBSTRATES SHALL CONSIST OF NON-CRACKED SOLID CONCRETE OR GROUT-FILLED CMU, 2000 PSI MIN.
6. SHIMS MUST BE USED WHEN GAP OF GREATER THAN 1/16" BETWEEN FRAME AND OPENING IS PRESENT AT THE ANCHOR LOCATION. MAX. SHIM STACK IS 1/4".
7. ONLY MIAMI-DADE COUNTY APPROVED CORROSION RESISTANT FASTENERS AND ITW TAPCON FASTENERS SHALL BE USED.
8. WINDOW INSTALLERS SHALL FOLLOW ALL MANUFACTURER'S INSTRUCTIONS.
9. NO SHUTTERS OR EXTERNAL PROTECTION DEVICES ARE REQUIRED.
10. GLAZING INDICATED HEREIN COMPLIES WITH ASTM E 1300-04.



DESIGN PRESSURE RATING	IMPACT RATING
+50.0 PSF -50.0 PSF	LARGE MISSILE




TABLE OF CONTENTS	
SHEET #	DESCRIPTION
1	GENERAL NOTES & TYPICAL ELEVATIONS
2	VERTICAL CROSS SECTIONS - 07-09 RETRO / 07-10 FLANGE
3	VERTICAL CROSS SECTION - 07-20 / NAILING FIN
4	HORIZONTAL CROSS SECTIONS - 07-09 / 07-10 / 07-20
5	ANCHORING LOCATIONS & GLAZING DETAILS (RETRO & FLANGE)
6	ANCHORING LOCATIONS & GLAZING DETAILS (NAILING FIN)
7	COMPONENTS & BILL OF MATERIALS

<p>1 Cochrane Avenue Pennsboro, WV 26415</p>	SIZE: B DRAWN BY: LMH CHECKED BY:	DRAWING NO.: DA0014 DATE: 02/01/17 DATE:	REV.: - DATE:
	SCALE: FIT SHEET: 1 of 7	APPR'V'D BY:	DATE: