



**THROUGH FRAME  
INSTALLATION**



<b>MAXIMUM FRAME</b>	<b>DP</b>	<b>IMPACT</b>
<b>73.875" x 81.50"</b>	<b>+60/-60</b>	<b>YES</b>
<b>WINDZONE 3</b>		

- Installation Notes:**
1. Seal flange/frame to substrate. Sill shall be set on a continuous serpentine bead of structural grade silicone caulk (typ.).
  2. Use #8 PH or greater fastener through the head, threshold & side jambs with sufficient length to penetrate a minimum of 1 1/2" into the wood framing. For 2x wood frame substrate (min. S.G. = 0.42)
  3. Host structure (wood buck, masonry, steel) to be designed and anchored to properly transfer all loads to the structure. The host structure is the responsibility of the architect or engineer of record for the project of installation.

- General Notes:**
1. The product shown herein is designed, tested and manufactured to comply with the wind load criteria of the adopted International Building Code (IBC), the International Residential Code (IRC), the Florida Building Code (FBC) and the industry requirement for the stated conditions.
  2. All glazing shall conform to ASTM E1300.
  3. At minimum, glazing is 3.0 mm tempered - 2.20 mm Kuraray PVB - 3.0 mm tempered - 14.0 mm airspace - 3.0 mm tempered glass.
  4. Use structural or composite shims where required.

This schedule addresses only the fasteners required to anchor the unit to achieve the rated design pressure and impact performance. (Where applicable) up to the size limitations noted. It is not intended as a guide to the installation process and does not address the sealing consideration that may arise in different wall conditions. For the complete installation procedure, see the instructions packaged with the unit or go to [www.jeld-wen.com/resources/installation](http://www.jeld-wen.com/resources/installation).

**DISCLAIMER:**  
This drawing and its contents are confidential and are not to be reproduced or copied in whole or in part or used or disclosed to others except as authorized by JELD-WEN Inc.

**"AS TESTED"**

DATE: 03/05/20	<b>JELD-WEN</b> 3737 LAKEPORT BLVD. KAMATH FALLS OR, 97601 PHONE: (800) 535-3936
SCALE: NTS	
TITLE: ARCHITECTURAL FIBERGLASS INSWING GLAZED FULL LITE DOUBLE DOOR	
DRAWN BY: I. BROOKS	
CHECKED BY: D. VEZO	
APPROVED BY: D. VEZO	
PART/PROJECT No.: D015723	
IDENTIFIER No. NCTL-310-19-132	
CAD DWG. No.:	
REV:	
SHEET 1 OF 1	