MASONITE.

HPC FIBERGLASS DOOR UNIT 6'-8" DOUBLE DOOR WITH / WITHOUT SIDELITES

GENERAL NOTES


- 1. EVALUATED FOR USE IN LOCATIONS ADHERING TO THE FLORIDA BUILDING CODE AND WHERE PRESSURE REQUIREMENTS AS DETERMINED BY ASCE 7, MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES, DOES NOT EXCEED THE DESIGN PRESSURES LISTED.
- 2. WHEN INSTALLED IN THE HIGH VELOCITY HURRICANE ZONE (HVHZ), HURRICANE PROTECTIVE SYSTEM (SHUTTERS) IS REQUIRED.
- 3. WHEN INSTALLED IN THE WIND-BORNE DEBRIS REGION, HURRICANE PROTECTIVE SYSTEM (SHUTTERS) IS REQUIRED.
- POLYURETHANE CORE FLAME SPREAD INDEX OF 50 AND SMOKE DEVELOPED INDEX OF 60 PER ASTM E84.
- 5. PLASTICS TESTING:

1 2 10 1100 120 11101			
TEST DESCRIPTION	DESIGNATION	FACING	LITE FRAME
SELF IGNITION TEMP	ASTM D1929	752 °F > 650 °F	740 °F > 650 °F
RATE OF BURNING	ASTM D635	0.56 IN/MIN	0.77 IN/MIN
SMOKE DENSITY	ASTM D2843	53.4%	13.4%
TENSILE STRENGTH*	ASTM D638	3.2% DIFF	7.1% DIFF

6. PLASTICS TESTING OF WORLDWIDE COMPOSITE FRAME (WHERE USED):

TEST DESCRIPTION	DESIGNATION	RESULT
SELF IGNITION TEMP	ASTM D1929	779 °F > 650 °F
RATE OF BURNING	ASTM D635	0.0 IN/MIN
SMOKE DENSITY	ASTM D2843	39.0%
TENSILE STRENGTH*	ASTM D638	3.6% DIFF

- * COMPARATIVE TENSILE STRENGTH AFTER WEATHERING 4500 HOURS XENON ARC METHOD 1
- 7. DOOR SLABS MUST BE STAMPED "HPC" ON TOP RAIL.








DOUBLE DOOR UNIT




SINGLE DOOR UNIT WITH SIDELITE



SINGLE DOOR UNIT WITH SIDELITE




SINGLE DOOR UNIT W/SIDELITES



DOUBLE DOOR UNIT W/SIDELITES

DESIGN PRESSURE RATING (1:1 OVERHANG OR WHERE NO WATER REQUIRED)				0)	WHERE WATER INFILTRATION PERFORMANCE IS REQUIRED TO BE 15% OF DESIGN PRESSURE						
CONFIG	MAX WIDTH	INS	WING	OUTSWING	INSWING	BUMPER O/S	Z-SERIES O/S	HP O/S	T4 0/S	HIGH DAM O/S	
X	37.5"	+50.0	-50.0	+50.0 / -50.0	N/A	+25.0 / -50.0	+40.0 / -50.0	+50.0 / -50.0	+50.0 / -50.0	+50.0 / -50.0	
XX	74"	+50.0	-50.0	+50.0 / -50.0	N/A	+25.0 / -50.0	+40.0 / -50.0	N/A	+50.0 / -50.0	+50.0 / -50.0	
OX or XO	75"	+50.0	-50.0	+50.0 / -50.0	N/A	+25.0 / -50.0	+40.0 / -50.0	N/A	+50.0 / -50.0	+50.0 / -50.0	
OXO	112.5"	+50.0	-50.0	+50.0 / -50.0	N/A	+25.0 / -50.0	+40.0 / -50.0	N/A	+50.0 / -50.0	+50.0 / -50.0	
OXXO	149"	+50.0	-50.0	+50.0 / -50.0	N/A	+25.0 / -50.0	+40.0 / -50.0	N/A	+50.0 / -50.0	+50.0 / -50.0	

	_		
		TABLE OF CONTENTS	
SHEET	#	DESCRIPTION	
1		TYPICAL ELEVATIONS & GENERAL NOTES	
2		ANCHORING LOCATIONS & DETAILS	
3		ANCHORING LOCATIONS & DETAILS	



DOUBLE DOOR UNIT W/SIDELITES



KURT BALTHAZOR FLORIDA P.E. #56533

CHK. BY:


DRAWING NO .:


DWG-MA-FL0191-17

SHEET 1 OF 3

5 MASONITE INTERNATIONAL CORP.
1955 POWIS ROAD
WEST CHICAGO, IL 6018! ROAD 18 WEST


PRODUCT:	"EXTERIOR DOOR PRODUCT"	DOUBLE 6'8" GLAZED	FIBERGLASS DOOR	PART OR ASSEMBLY:		& GENERAL NOTES		
	SMS	SWS	SWS	SWS	SWS	ВУ		
	CORRECTIONS	TEXT CORRECTIONS	MISC UPDATE	ADDED HP	UPDATED DATA		REVISIONS	
	7/1/25	AI.	7/18/20	5/2/18	11/27/17	DATE		
	ш	D	ပ	മ	A	NO.		
DA	TE:	4,	/2	6,	/1	7		
_	SCALE: N.T.S. DWG. BY: SWS							
DWG. BY: SWS								







ATTACHMENT DETAIL

- 1. ANCHOR ANALYSIS FOR LOADING CONDITIONS PREPARED, SIGNED AND SEALED BY ROBERTO LOMAS, P.E. (FLORIDA #62514) WITH THE LOWEST (LEAST) FASTENER RATING FROM THE DIFFERENT FASTENERS BEING CONSIDERED FOR USE. JAMB, HEAD, AND THRESHOLD FASTENERS ANALYZED FOR THIS UNIT INCLUDE #10 WOOD SCREWS, 1/4" TAPCONS, AND #10 TEK SCREWS. A PHYSICAL SHIM MUST BE PLACED IN SHIM SPACE AT EACH ANCHOR LOCATION. TAPCON EDGE DISTANCE MIN 2-1/2". WOOD SCREW EDGE DISTANCE MIN 3/4". TEK SCREW EDGE DISTANCE MIN 1/2".
- 2. ANCHORING INTO STEEL STRUCTURE MUST BE SUFFICIENT TO ACHIEVE 3 THREADS MINIMUM BEYOND STEEL INTERIOR SURFACE.
- 3. THE WOOD SCREW SINGLE SHEAR DESIGN VALUES COME FROM ANSI/AF&PA NDA FOR SOUTHERN PINE LUMBER AND ACHEIVEMENT OF 1-1/2" MINIMUM EMBEDMENT. THE TAPCON MUST ACHIEVE MINIMUM EMBEDMENT OF 1-1/4".
- 4. WOOD BUCKS BY OTHERS MUST BE ANCHORED PROPERLY TO TRANSFER LOADS TO STRUCTURE.
- 5. MINIMUM DESIGN VALUE STRENGTH OF ANCHORS 155 LBS.




1X BUCK MASONRY






COMBINATION WOOD

MULLION (BOXED)



TYPICAL WOOD BUCK ANCHOR INSTALLATION



INTEGRAL WOOD MULLION (CHS)



INTEGRAL WW MULLION (CHS)

COMBINATION WOOD

MULLION (BOXED)

	_	
MASONITE	1955	WEST C
INTERNAT	POWIS ROAD	CHICAGO.
MASONITE INTERNATIONAL CORP.	ROAD	11 60185

PRODUCT:	"EXTERIOR DOOR PRODUCT"		DOUBLE DOOR UNIT	S PART OR ASSEMBLY:	ANCHORING LOCATIONS	& DFTAILS
	S	S	Ś	S	S	

_	_		_	_	_	_	_
	SWS	SWS	SWS	SWS	SMS	ВҮ	
	CORRECTIONS	TEXT CORRECTIONS	MISC UPDATE	ADDED HP	UPDATED DATA		REVISIONS
	7/1/25	10/31/22	7/18/20	5/2/18	11/27/17	DATE	
	ш		ပ			NO.	
DA	TE:	4	/2	26,	/1	7	
sc	ALE	:	١	V.T	S.		
DW	IG.	BY:		S	W:	S	

CHK. BY:

DRAWING NO.:

DWG-MA-FL0191-17

SHEET 3 OF 3