




**SERIES 9000, MODEL 9500 (OX/XO) &  
SERIES 9000, MODEL 9500-3 (XOX)  
HORIZONTAL ROLLER WINDOW,  
NON-IMPACT RESISTANT,  
FLANGE, EQUAL-LEG & FIN FRAMES**

FLORIDA PRODUCT APPROVAL #39124

DP RATING SEE TABLES 1 & 2	NOT RATED FOR MISSILE IMPACT RESISTANCE
-------------------------------	---



A. LYNN MILLER, P.E., P.E.# 58705

1) THIS PRODUCT HAS BEEN DESIGNED & TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE, EXCLUDING THE HIGH VELOCITY HURRICANE ZONE (HVHZ).

2) SHUTTERS ARE REQUIRED WHEN USED IN WIND-BORNE DEBRIS REGIONS.

3) MASONRY ANCHORS MAY BE USED INTO WOOD. ALL WOOD BUCKS LESS THAN 1-1/2" THICK ARE TO BE CONSIDERED 1X INSTALLATIONS. 1X WOOD BUCKS ARE OPTIONAL IF UNIT IS INSTALLED DIRECTLY TO SUBSTRATE. WOOD BUCKS DEPICTED AS 2X ARE 1-1/2" THICK OR GREATER.

4) ANCHOR EMBEDMENT TO BASE MATERIAL SHALL BE BEYOND WALL DRESSING OR STUCCO. USE ANCHORS OF SUFFICIENT LENGTH.

5) MAX. 1/4" SHIMS ARE REQUIRED AT EACH ANCHOR LOCATION WHERE THE PRODUCT IS NOT FLUSH TO THE SUBSTRATE. USE SHIMS CAPABLE OF TRANSFERRING APPLIED LOADS.

6) THE ANCHORAGE METHODS SHOWN HAVE BEEN DESIGNED TO RESIST THE WIND LOADS CORRESPONDING TO THE REQUIRED DESIGN PRESSURE. THE 33-1/3% STRESS INCREASE HAS NOT BEEN USED IN THE DESIGN OF THIS PRODUCT. THE 1.6 LOAD DURATION FACTOR WAS USED FOR THE EVALUATION OF ANCHORS INTO WOOD. ANCHORS THAT COME INTO CONTACT WITH OTHER DISSIMILAR MATERIALS SHALL MEET THE REQUIREMENTS OF THE FLORIDA BUILDING CODE FOR CORROSION RESISTANCE.




TABLE 1: DESIGN PRESSURES

Buck Width	Buck Height	Configuration	Impact Level	Frame Type	Glass Type	Design Pressure	
						(+) psf	(-) psf
74"	62"	XO/OX	Non-Impact	Flange, Equal-Leg	1 or 2	45.0	45.0
74"	62"	XO/OX	Non-Impact	Flange, Equal-Leg	3 or 4	55.0	65.0
60"	60"	XO/OX	Non-Impact	Flange, Equal-Leg	1 or 2	55.0	55.0
74"	62"	XO/OX	Non-Impact	Integral Fin	1 or 2	45.0	45.0
74"	62"	XO/OX	Non-Impact	Integral Fin	3 or 4	55.0	60.0
60"	60"	XO/OX	Non-Impact	Integral Fin	1 or 2	50.0	50.0

FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE WIDTH OR HEIGHT DIMENSION.  
FOR GLASS TYPES, SEE SHEET 7.

REGISTRATION #29296

COPYRIGHT © 2021  
NEWSOUTH WINDOW SOLUTIONS  
LIMITED LICENSE TO MAKE  
COPIES FOR PERMITTING


PREPARED BY: A. LYNN MILLER, P.E.  
1070 TECHNOLOGY DR  
N. VENICE, FL 34275  
(941)-480-1600

9000 SERIES HORIZ. ROLLER  
MODELS 9500 & 9500-3, NI  
GENERAL NOTES, XO DESIGN  
PRESSURES & ANCHOR ELEVATION  
NEWSOUTH WINDOW SOLUTIONS  
10741 CROSSROADS COMMERCE BLVD.  
TAMPA, FL 33610


BY:	LY	SB	
REVISION:	MINOR EDITORIAL UPDATES	ADD 995 SILICONE TO BOM	
DATE:	12/22	8/16/23	
#:	1	2	
DATE:	12/14/2022		
SCALE:	NTS		
BY:	LOGAN YODER		
DRAWING #:	HR9000-FPA-NI		
SHEET:	1 OF 7		



A. LYNN MILLER, P.E., P.E.# 58705



TYP. ANCHOR LOCATIONS  
(FLANGE FRAME SHOWN, EQUAL-LEG SIMILAR)  
(1/4 - 1/2 - 1/4 CONFIGURATION SHOWN)



TYP. ANCHOR LOCATIONS  
(FIN FRAME SHOWN)  
(1/4 - 1/2 - 1/4 CONFIGURATION SHOWN)


TABLE 2:

Buck Width	Buck Height	Configuration	Impact Level	Frame Type	Glass Types	Design Pressure	
						(+) psf	(-) psf
82-7/8"	63"	XOX, (1/3, 1/3, 1/3)	Non-Impact	Flange, Equal-Leg	Operable Lite: 1-4	50.0	50.0
					Fixed Lite: 1-4		
82-7/8"	63"	XOX, (1/3, 1/3, 1/3)	Non-Impact	Fin	Operable Lite: 1-4	45.0	45.0
					Fixed Lite: 1-4		
111"	63"	XOX, (1/4, 1/2, 1/4)	Non-Impact	Flange, Equal-Leg	Operable Lite: 1-4	50.0	50.0
					Fixed Lite, See Table 2A		
111"	63"	XOX, (1/4, 1/2, 1/4)	Non-Impact	Fin	Operable Lite: 1-4	45.0	45.0
					Fixed Lite, See Table 2A		

TABLE 2A:

Allowable Glass Types for the Fixed Lite of an XOX 1/4 - 1/2 - 1/4							
		Width					
		60"	72"	84"	96"	108"	111"
Height	36"	1 - 4	1 - 4	1 - 4	1 - 4	1 - 4	1 - 4
	48"	1 - 4	1 - 4	1 - 4	1 - 4	2 - 4	2 - 4
	54"	1 - 4	1 - 4	1 - 4	2 - 4	2 - 4	2 - 4
	60"	1 - 4	1 - 4	2 - 4	2 - 4	3 & 4	3 & 4
	63"	1 - 4	1 - 4	2 - 4	2 - 4	3 & 4	3 & 4

- 1) FOR SIZES NOT SHOWN, ROUND UP TO THE NEXT AVAILABLE WIDTH OR HEIGHT DIMENSION.
- 2) FOR GLASS DESCRIPTIONS, SEE SHEET 7.
- 3) BUCK DIMENSIONS SHOWN.



WINDOW MAY BE A 1/4 - 1/2 - 1/4 CONFIGURATION OR 1/3 - 1/3 - 1/3 CONFIGURATION PROVIDED DLO (DAYLITE OPENING) SIZES ARE NOT EXCEEDED.

REGISTRATION #29296  
COPYRIGHT © 2021  
NEWSOUTH WINDOW SOLUTIONS  
LIMITED LICENSE TO MAKE  
COPIES FOR PERMITTING

PREPARED BY: A. LYNN MILLER, P.E.  
1070 TECHNOLOGY DR  
N. VENICE, FL 34275  
(941)-480-1600

9000 SERIES HORIZ. ROLLER MODELS 9500 & 9500-3, NI	GENERAL NOTES, XOX DESIGN PRESSURES & ANCHOR ELEVATION	NEWSOUTH WINDOW SOLUTIONS 10741 CROSSROADS COMMERCE BLVD. TAMPA, FL 33610
BY: LY SB	REVISION:	
DATE: 12/22	MINOR EDITORIAL UPDATES	
#: 1	ADD 995 SILICONE TO BOM	
DATE: 12/14/2022		
SCALE: NTS		
BY: LOGAN YODER		
DRAWING #: HR9000-FPA-NI		
SHEET: 2 OF 7		



A. LYNN MILLER, P.E., P.E.# 58705

REGISTRATION #29296  
 PREPARED BY: A. LYNN MILLER, P.E.  
 1070 TECHNOLOGY DR  
 N. VENICE, FL 34275  
 (941)-480-1600


COPYRIGHT © 2021  
 NEWSOUTH WINDOW SOLUTIONS  
 LIMITED LICENSE TO MAKE  
 COPIES FOR PERMITTING

9000 SERIES HORIZ. ROLLER  
 MODELS 9500 & 9500-3, NI  
 FLANGE INSTALLATION & ANCHOR TYPES  
 NEWSOUTH WINDOW SOLUTIONS  
 10741 CROSSROADS COMMERCE BLVD.  
 TAMPA, FL 33610

BY:	LY	SB
REVISION:	MINOR EDITORIAL UPDATES	ADD 995 SILICONE TO BOM
DATE:	12/22	8/16/23
#:	1	2

DATE: 12/14/2022  
 SCALE: NTS  
 BY: LOGAN YODER  
 DRAWING #: HR9000-FPA-NI  
 SHEET: 3 OF 7

1 HEAD FLANGE FRAME X-SECTION INTO 2X WOOD OR MASONRY



2 SILL FLANGE FRAME X-SECTION INTO 2X WOOD OR MASONRY


TABLE 3: INSTALLATION ANCHORS

Anchor	Substrate	Minimum Edge Distance	Minimum Embedment
#10 or #12 Steel or 410 SS Screw	Southern Pine (SG = .55)	9/16"	1-3/8"
	Aluminum, 6063-T5 min.	3/8"	0.050"
	Steel Stud, Gr. 33 min.	3/8"	0.045" (20 Ga)
	A36 Steel	3/8"	0.050"
3/16" Steel Ultracon+	Concrete (min. 2.9 ksi)	1"	1-3/4"
	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"
	Southern Pine (SG = .55)	1"	1-3/8"
1/4" Steel Ultracon+	Concrete (min. 3.0 ksi)	1"	1-3/8"
	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"
	Southern Pine (SG = .55)	1"	1-3/8"

- ANCHOR MUST EXTEND A MINIMUM OF 3 THREADS BEYOND ANY METAL SUBSTRATE.
- "UNGROUTED CMU" VALUES MAY BE USED FOR GROUTED CMU APPLICATIONS.
- ALL ANCHOR HEAD TYPES ARE APPLICABLE.

INSTALLATION NOTES:

- SEE SHEET 1 FOR ANCHOR SPACING REQUIREMENTS.
- ANY INSTALLATION OPTION SHOWN (2X BUCK OR WOOD FRAMING, 1X BUCK, DIRECT TO MASONRY, STEEL STUD) MAY BE USED ON ANY SIDE OF THE WINDOW.
- USE ONLY SUBSTRATE APPROPRIATE ANCHORS LISTED IN ANCHOR TABLE 3. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. MAX. SHIM THICKNESS TO BE 1/4".



3 JAMB FLANGE FRAME X-SECTION THRU 1X INTO 2X WOOD OR MASONRY

4 MEETING RAIL X-SECTION SHOWN FOR OX CONFIGURATION (XOX SIMILAR)

5 JAMB FLANGE FRAME X-SECTION USING SCREWS INTO METAL



A. LYNN MILLER, P.E., P.E.# 58705

REGISTRATION #29296  
 COPYRIGHT © 2021  
 NEWSOUTH WINDOW SOLUTIONS  
 LIMITED LICENSE TO MAKE  
 COPIES FOR PERMITTING

9000 SERIES HORIZ. ROLLER  
 MODELS 9500 & 9500-3, NI  
 EQUAL-LEG INSTALLATION &  
 ANCHOR TYPES  
 NEWSOUTH WINDOW SOLUTIONS  
 10741 CROSSROADS COMMERCE BLVD.  
 TAMPA, FL 33610

PREPARED BY: A. LYNN MILLER, P.E.  
 1070 TECHNOLOGY DR  
 N. VENICE, FL 34275  
 (941)-480-1600

BY:	LY	SB
REVISION:	MINOR EDITORIAL UPDATES	ADD 995 SILICONE TO BOM
DATE:	12/22	8/16/23
#:	1	2

DATE: 12/14/2022  
 SCALE: NTS  
 BY: LOGAN YODER  
 DRAWING #: HR9000-FPA-NI  
 SHEET: 4 OF 7



TABLE 4: INSTALLATION ANCHORS

Anchor	Substrate	Minimum Edge Distance	Minimum Embedment
#10 or #12 Steel or 410 SS Screw	Southern Pine (SG = .55)	9/16"	1-3/8"
	Aluminum, 6063-T5 min.	3/8"	0.050"
	Steel Stud, Gr. 33 min.	3/8"	0.045" (20 Ga)
	A36 Steel	3/8"	0.050"
3/16" Steel Ultracon+	Concrete (min. 2.9 ksi)	1"	1-3/4"
	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"
	Southern Pine (SG = .55)	1"	1-3/8"
1/4" Steel Ultracon+	Concrete (min. 3.0 ksi)	1"	1-3/8"
	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"
	Southern Pine (SG = .55)	1"	1-3/8"

- ANCHOR MUST EXTEND A MINIMUM OF 3 THREADS BEYOND ANY METAL SUBSTRATE.
- "UNGROUTED CMU" VALUES MAY BE USED FOR GROUTED CMU APPLICATIONS.
- ALL ANCHOR HEAD TYPES ARE APPLICABLE.

INSTALLATION NOTES:

- SEE SHEET 1 FOR ANCHOR SPACING REQUIREMENTS.
- ANY INSTALLATION OPTION SHOWN (2X BUCK OR WOOD FRAMING, 1X BUCK, DIRECT TO MASONRY, STEEL STUD) MAY BE USED ON ANY SIDE OF THE WINDOW.
- USE ONLY SUBSTRATE APPROPRIATE ANCHORS LISTED IN ANCHOR TABLE 4. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. MAX. SHIM THICKNESS TO BE 1/4".




1 SILL EQUAL-LEG FRAME X-SECTION INTO 2X WOOD OR MASONRY

3 JAMB EQUAL-LEG FRAME X-SECTION THRU 1X INTO 2X WOOD OR MASONRY

4 MEETING RAIL X-SECTION SHOWN FOR OX CONFIGURATION (XOX SIMILAR)

5 JAMB EQUAL-LEG FRAME X-SECTION USING SCREWS INTO METAL



A. LYNN MILLER, P.E., P.E.# 58705

TABLE 5: INSTALLATION ANCHORS


Anchor	Substrate	Min. Edge Distance	Min. Embedment
2-1/2" x .113" Box Nail	P.T. Southern Pine (SG = .55)	5/16"	2-7/16"
2-1/2" x .131" Common Nail	P.T. Southern Pine (SG = .55)	3/8"	2-7/16"
2-1/2" x .145" Roofing Nail	P.T. Southern Pine (SG = .55)	3/8"	2-7/16"
#10 Steel SMS	P.T. Southern Pine (SG = .55)	1/2"	1-3/8"
	Aluminum, 6063-T5 min.	3/8"	1/8"
	Steel Stud, Gr. 33 min.	3/8"	0.036
	A36 Steel	3/8"	1/8"

- 1) ANCHOR MUST EXTEND A MINIMUM OF 3 THREADS BEYOND ANY METAL SUBSTRATE.
- 2) ALL ANCHOR HEAD TYPES ARE APPLICABLE.


INSTALLATION NOTES:

- 1) SEE SHEET 1 FOR SPACING REQUIREMENTS.
- 2) FLANGE AND/OR FIN MAY BE REMOVED TO CREATE OTHER FRAME TYPES.
- 3) USE ONLY SUBSTRATE APPROPRIATE ANCHORS LISTED IN ANCHOR TABLE 5. FOLLOW EMBEDMENT AND EDGE DISTANCE LIMITS. ANY INSTALLATION OPTION SHOWN MAY BE USED ON ANY OR ALL SIDES OF THE WINDOW.
- 4) MAX. SHIM THICKNESS TO BE 1/4". MAX. SHIM SPACING TO BE 18".

1 HEAD FIN FRAME X-SECTION USING NAILS INTO 2X WOOD




2 SILL FIN FRAME X-SECTION USING NAILS INTO 2X WOOD



3 JAMB FIN FRAME X-SECTION USING SCREWS INTO 2X WOOD

4 MEETING RAIL X-SECTION SHOWN FOR OX CONFIGURATION (XOX SIMILAR)



5 JAMB FIN FRAME X-SECTION USING SCREWS INTO METAL


REGISTRATION #29296  
 PREPARED BY: A. LYNN MILLER, P.E.  
 1070 TECHNOLOGY DR  
 N. VENICE, FL 34275  
 (941)-480-1600

COPYRIGHT © 2021  
 NEWSOUTH WINDOW SOLUTIONS  
 LIMITED LICENSE TO MAKE  
 COPIES FOR PERMITTING

9000 SERIES HORIZ. ROLLER  
 MODELS 9500 & 9500-3, NI  
 FIN INSTALLATION & ANCHOR TYPES  
 NEWSOUTH WINDOW SOLUTIONS  
 10741 CROSSROADS COMMERCE BLVD.  
 TAMPA, FL 33610

REVISION:	DATE:	#:	BY:
MINOR EDITORIAL UPDATES	12/22	1	LY
ADD 995 SILICONE TO BOM	8/16/23	2	SB


DATE: 12/14/2022  
 SCALE: NTS  
 BY: LOGAN YODER  
 DRAWING #: HR9000-FPA-NI  
 SHEET: 5 OF 7




1 FRAME, FLANGE

2 FRAME, EQUAL-LEG


3 FRAME, FIN




4 SASH TOP RAIL




5 SASH BOTTOM RAIL




6 SASH HANDLE STILE




7 SASH LOCK RAIL




8 SASH MEETING RAIL




9 GLAZING BEAD




10 GLAZING BEAD




12 REINFORCEMENT (@ MEETING RAIL)




13 REINFORCEMENT (@ LOCK RAIL)




14 REINFORCEMENT (@ HANDLE STILE)




15 ANTI-LIFT RAIL



16 ROLLER TRACK



17 SILL RISER



40 SCREEN

TABLE 6:

BILL OF MATERIALS			
ITEM #	PART #	DESCRIPTION	MATERIAL
1		Frame, Flange	PVC
2	9439	Frame, Equal-Leg	PVC
3		Frame, Fin	PVC
4	9478	Sash Top Rail	PVC
5	9424	Sash Bottom Rail	PVC
6	9475	Sash Handle Stile	PVC
7	9476	Sash Lock Rail	PVC
8	9477	Sash Meeting Rail	PVC
9	9436	Glazing Bead	PVC
10	9425	Glazing Bead	PVC
12	6165	Reinforcement @ Meeting Rail	6063-T6
13	6163	Reinforcement @ Lock Rail	6063-T6
14	6166	Reinforcement @ Handle Stile	6063-T6
15	6162	Anti-Lift Rail	6063-T6
16	6161	Roller Track	6063-T6
17	6158	Sill Riser	6063-T6
20		Lock	
22		Keeper	
24	8153	Roller Assm.	
25	8223	Weep Cover	Composite
26	4007	Weatherstrip, .270" x .250" Polyfin	
30	1003	Screw, #6 x 1/2" PFH	Steel
31	1007	Screw, #6 x 1-1/4" PFH	Steel
32	1012	Screw, #6 x 3/4" PFH	Steel
33	1015	Screw, #8 x 1/2" PTRUSS	Steel
34	1067	Screw, #6 x 3/8" PPH	Steel
35		RGS7700, Sika 552, Dow 791/983/995 Backbedding	
36		IG Spacer	varies
37		Setting Block	varies
40	6244	Screen	Nylon

THE APPROVED, RIGID PVC EXTERIOR EXTRUSIONS ARE TO BE PRODUCED BY EXTRUDERS' LICENSEES UNDER "AAMA CERTIFICATION PROGRAMS FOR RIGID PVC EXTRUSIONS".



A. LYNN MILLER, P.E., P.E.# 58705

REGISTRATION #29296

COPYRIGHT © 2021  
NEWSOUTH WINDOW SOLUTIONS  
LIMITED LICENSE TO MAKE  
COPIES FOR PERMITTING

PREPARED BY: A. LYNN MILLER, P.E.  
1070 TECHNOLOGY DR  
N. VENICE, FL 34275  
(941)-480-1600

9000 SERIES HORIZ. ROLLER  
MODELS 9500 & 9500-3, NI

EXTRUSIONS & BOM  
NEWSOUTH WINDOW SOLUTIONS  
10741 CROSSROADS COMMERCE BLVD.  
TAMPA, FL 33610

REVISION:	DATE:	#:	BY:
MINOR EDITORIAL UPDATES	12/22	1	LY
ADD 995 SILICONE TO BOM	8/16/23	2	SB

DATE: 12/14/2022

SCALE: NTS

BY: LOGAN YODER

DRAWING #: HR9000-FPA-NI

SHEET: 6 OF 7



A. LYNN MILLER, P.E., P.E.# 58705

REGISTRATION #29296


COPYRIGHT © 2021  
NEWSOUTH WINDOW SOLUTIONS  
LIMITED LICENSE TO MAKE  
COPIES FOR PERMITTING

PREPARED BY: A. LYNN MILLER, P.E.  
1070 TECHNOLOGY DR  
N. VENICE, FL 34275  
(941)-480-1600


9000 SERIES HORIZ. ROLLER  
MODELS 9500 & 9500-3, NI  
WOOD BUCK INSTALLATION &  
GLASS TYPES  
NEWSOUTH WINDOW SOLUTIONS  
10741 CROSSROADS COMMERCE BLVD.  
TAMPA, FL 33610

BY:	LY	SB	
REVISION:	MINOR EDITORIAL UPDATES	ADD 995 SILICONE TO BOM	
DATE:	12/22	8/16/23	
#:	1	2	

DATE: 12/14/2022  
SCALE: NTS  
BY: LOGAN YODER  
DRAWING #: HR9000-FPA-NI  
SHEET: 7 OF 7



XO/OX BUCK ANCHORAGE DETAIL



XOX BUCK ANCHORAGE DETAIL

TABLE 7:

Anchor	Substrate	Minimum Edge Distance	Minimum Embedment
1/4" Steel Ultracon+	Concrete (min. 3.0 ksi)	1"	1-3/8"
	UngROUTED CMU, (ASTM C-90)	1"	1-1/4"

- 1) "UNGROUTED CMU" VALUES MAY BE USED FOR GROUTED CMU APPLICATIONS.
- 2) ALL ANCHOR HEAD TYPES ARE APPLICABLE.

