

# **GLICK METALS LLC**

## **MIAMI-DADE**

## **TEST REPORT**

**SCOPE OF WORK**

TAS 100(A) TESTING ON SNAP-Z, RIDGE VENT

**REPORT NUMBER**

K8029.01-109-18

**TEST DATE**

11/18/20

**ISSUE DATE**

12/08/20

**MIAMI-DADE COUNTY NOTIFICATION NO.**

ATI 20073

**LABORATORY CERTIFICATION NO.**

19-0321.16


**PAGES**

15

**DOCUMENT CONTROL NUMBER**

RT-R-AMER-Test-7808 (05/23/19)

© 2019 INTERTEK





## TEST REPORT FOR GLICK METALS LLC

Report No.: K8029.01-109-18

Date: 12/08/20

### REPORT ISSUED TO

#### GLICK METALS LLC

330 Swamp Road

Morgantown, Pennsylvania 19543

### SECTION 1

#### SCOPE


Intertek Building & Construction (B&C) was contracted by Glick Metals LLC to perform TAS 100(A) testing in accordance with Miami-Dade County requirements on Snap-Z, ridge vent. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at the Intertek B&C test facility in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. Intertek B&C will service this report for the entire test record retention period. The test record retention period ends ten years after the test date. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained for the entire test record retention period

### SECTION 2

#### SUMMARY OF TEST RESULTS


The specimen tested met the performance requirements set forth in the protocols.



For INTERTEK B&C:

<b>COMPLETED BY:</b>	Kyle W. Ruth Technician – Product Testing
<b>TITLE:</b>	
<b>SIGNATURE:</b>	 <small>Digitally Signed by: Kyle Ruth</small>
<b>DATE:</b>	12/08/20

KWR:nls

<b>REVIEWED BY:</b>	Daniel C. Culbert, P.E.
<b>TITLE:</b>	Senior Project Engineer
<b>SIGNATURE:</b>	 <small>Digitally Signed by: Daniel Craig Culbert</small>
<b>DATE:</b>	12/08/20

2020.12.08 17:00:12 -05'00'

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



## TEST REPORT FOR GLICK METALS LLC

Report No.: K8029.01-109-18

Date: 12/08/20

### SECTION 3

#### TEST METHOD(S)

The specimen was evaluated in accordance with the following:

**TAS 100(A)-95**, *Test Procedure for Wind and Wind Driven Rain Resistance and/or Increased Windspeed Resistance of Soffit Ventilation Strip and Continuous or Intermittent Ventilation System Installed at the Ridge Area*

### SECTION 4

#### MATERIAL SOURCE

Test sample materials were provided by the client from Glick Metals LLC facility located in Morgantown, Pennsylvania. Representative samples of the test specimen will be retained by Intertek B&C for a minimum of ten years from the test completion date.

### SECTION 5

#### EQUIPMENT/CALIBRATION

Vane Axial Fan – Y003346

Stopwatch – INT00974

Weather Station - 63317

Windstream, water supply, and water distribution calibration were performed prior to testing. Reference Intertek B&C Calibration Report No. L0971.03-109-18, dated 07/01/20, for descriptions and results.

### SECTION 6

#### LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Manny Glick	Glick Metals LLC
John Lapp	Glick Metals LLC
Andrew P. Mehalick	Intertek B&C
Kyle W. Ruth	Intertek B&C



**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18

Date: 12/08/20

**SECTION 7****TEST SPECIMEN DESCRIPTION****Manufacturer:** Glick Metals LLC**Product Type:** Ridge Vent**Series/Model:** Snap-Z

**Roof Deck Description:** An 8' 0" wide by 6' 0" long roof deck on a 2:12 slope was utilized. The roof deck consisted of #2 Spruce-Pine-Fir nominal 2x6 intermediate supports sheathed with APA 32/16 span rated 15/32" plywood sheathing. The intermediate supports were spaced 24" on center. The plywood was secured to the rafters with 1-5/8" bugle head screws spaced 6" on center around the perimeter and 12" on center at the intermediate supports. The roof deck was covered with 30# felt underlayment. 16" wide, 24-gauge steel standing seam roof panels were installed over the felt and secured with #10 x 1" pancake head screws. A 2" wide by 84" long opening was cut into the ridge for ventilation of the vent.

**Ridge Vent Description:** The ridge vent was composed of 15-7/8" long sections of formed 24-gauge steel sheet and open cell foam. The leading face of the vent sections were punched to allow airflow through the foam. The foam measured 1" thick by 1-3/4" tall and was pressed into the formed vent section. The vent was secured to the test deck with #10 x 1" screws spaced at 3" on center. A strip of butyl tape was utilized under the attachment leg sealing to the roof deck. The leading edge and each end of the vent sections were sealed with silicone. An aluminum sheet ridge cap was then secured over the ridge with #10 x 3/4" hex head screws with sealing washers.



## TEST REPORT FOR GLICK METALS LLC

Report No.: K8029.01-109-18

Date: 12/08/20

### SECTION 8

#### TEST RESULTS

**Protocol TAS 100(A)-95, Test Procedure for Wind and Wind Driven Rain Resistance and/or Increased Windspeed Resistance of Soffit Ventilation Strip and Continuous or Intermittent Ventilation System Installed at the Ridge Area**

**Test Date(s):** 11/18/20

The temperature during testing was 6°C (42°F). The results are tabulated as follows:

**Test Procedure:** The wind speed intervals were conducted as follows:

Interval No.	Wind Speed (mph)	Time (min)	Water Spray
1	35	15	On
2	0	5	Off
3	70	15	On
4	0	5	Off
5	90	15	On
6	0	5	Off
7	110	5	On
8	0	5	Off

**Test Results:** The TAS 100(A) test results are as follows:

Wind Speed	Results
35 mph	0 oz.
70 mph	0 oz.
90 mph	0 oz.
110 mph	0 oz.

**Result(s):** Pass

#### General Notes

*Tested at a 2:12 roof pitch.*

*During the 110 mph wind speed interval, droplets of water were observed on the collection bag that were not measurable.*



## TEST REPORT FOR GLICK METALS LLC


Report No.: K8029.01-109-18

Date: 12/08/20

### SECTION 9 PHOTOGRAPHS



**Photo No. 1**  
**Top Side Before Testing**



**Photo No. 2**  
**Underside Before Testing**



## TEST REPORT FOR GLICK METALS LLC

Report No.: K8029.01-109-18

Date: 12/08/20



**Photo No. 3**  
**35 MPH Top Side**




**Photo No. 4**  
**35 MPH Underside**



**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18

Date: 12/08/20



**Photo No. 5**  
**70 MPH Top Side**



**Photo No. 6**  
**70 MPH Underside**



## TEST REPORT FOR GLICK METALS LLC

Report No.: K8029.01-109-18

Date: 12/08/20



**Photo No. 7**  
**90 MPH Top side**




**Photo No. 8**  
**90 MPH Underside**




**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18

Date: 12/08/20



**Photo No. 9**  
**110 MPH Top Side**



**Photo No. 10**  
**110 MPH Underside**



**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18

Date: 12/08/20



**Photo No. 11**  
**Post Test Top Side**



**Photo No. 12**  
**Post Test Underside**





Total Quality. Assured.

130 Derry Court  
York, Pennsylvania 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18


Date: 12/08/20

**SECTION 10**

**DRAWINGS**

The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.





### Snap-Z Ridge Detail

Not To Scale

Models Available:

Snap-Z 1000	1" rib height
Snap-Z 1500	1 1/2" rib height
Snap-Z 1750	1 3/4" rib height
<b>Snap-Z 2000</b>	<b>2" rib height</b>

**intertek**  
Total Quality Assured.


Report #: K8029.01-109-18

Date: 12/1/20


Verified by: *[Signature]*



End View




15-7/8"



13 lances per row (6 rows)  
78 lances per lin ft  
12.168 sq in net free area per lin ft

Front Side

15-7/8"



Back Side

Snap-Z 2000 Detail  
Not To Scale





Total Quality. Assured.

130 Derry Court  
York, Pennsylvania 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

**TEST REPORT FOR GLICK METALS LLC**

Report No.: K8029.01-109-18

Date: 12/08/20

**SECTION 11**

**REVISION LOG**

REVISION #	DATE	PAGES	REVISION
0	12/08/20	N/A	Original Report Issue