


PICTURE WINDOW - NON-IMPACT



GENERAL NOTES:

1. THE PRODUCT SHOWN HEREIN IS DESIGNED AND MANUFACTURED TO COMPLY WITH THE FLORIDA BUILDING CODE (FBC), CURRENT EDITION AND IS RATED FOR USE IN THE HIGH VELOCITY HURRICANE ZONE (HVHZ).
2. GLAZING OPTIONS: (SEE SHEET 3)
3. CONFIGURATIONS: "O". ARCHITECTURAL SHAPES INCLUDE, BUT ARE NOT LIMITED TO, THOSE SHOWN ON SHEET 2.
4. DESIGN PRESSURE RATING (SEE SHEET 3):
-NEGATIVE DESIGN LOADS BASED ON, TESTED PRESSURE AND GLASS TABLES ASTM E-1300-04e01/09.
-POSITIVE DESIGN LOADS BASED ON, TESTED PRESSURE, WATER INFILTRATION TEST PRESSURE AND GLASS TABLES ASTM E-1300-04e01/09.
5. ANCHORAGE: THE 33 1/3% STRESS INCREASE HAS NOT BEEN USED IN THE DESIGN OF THIS PRODUCT. SEE SHEET 7 FOR ANCHOR DETAILS. WINDLOAD DURATION FACTOR Cd=1.6 WAS USED FOR WOOD ANCHOR CALCULATIONS.
6. NOT APPROVED FOR IMPACT RESISTANCE. IMPACT PROTECTIVE SYSTEM IS REQUIRED IN WIND BORNE DEBRIS REGION.
7. ALL FRAMES FULLY WELDED.
8. SERIES / MODEL DESIGNATION PW-8150.
9. THE DESIGNATION X AND O STAND FOR THE FOLLOWING:
O = FIXED SASH
10. SECTION CALLOUTS APPLY TO ALL ELEVATIONS IN A SIMILAR LOCATION.
11. PICTURE WINDOWS CAN BE INSTALLED IN ANY ORIENTATION



8150 PVC PICTURE WINDOW NON-IMPACT

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF CUSTOM WINDOW SYSTEMS, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF CUSTOM WINDOW SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:
4093



8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering & Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:
GENERAL NOTES AND ELEVATIONS

DRAWN BY: MCS	DATE: 8/3/2023
DWG #: CWS-506	REV.: E
SCALE: 1:20	SHEET 1 OF 7

TABLE OF CONTENTS

GENERAL NOTES & ELEVATIONS.....	1
ARCHITECTURAL SHAPES.....	2
COMPARATIVE ANALYSIS & GLAZING DETAILS....	3
SECTION VIEWS.....	4
DP CHART, BOM & EXTRUSIONS.....	5
ANCHOR SCHEDULE & NOTES.....	6
INSTALLATION DETAILS.....	7

MAX. UNIT SIZE	DESIGN PRESSURE RATING	IMPACT RATING
50" x 72"	SEE COMPARATIVE ANALYSIS CHART, SHEET 3	NONE




1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

**8150 PVC
PICTURE WINDOW
NON-IMPACT**

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN
THIS DRAWING IS THE SOLE
PROPERTY OF CUSTOM WINDOW
SYSTEMS, INC. ANY
REPRODUCTION IN PART OR AS A
WHOLE WITHOUT THE WRITTEN
PERMISSION OF CUSTOM WINDOW
SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:

4093



8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering &
Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:

**ARCHITECTURAL
SHAPES**

DRAWN BY:

MCS

DATE:

8/3/2023

DWG #:

CWS-506

REV.:


E

SCALE:


1:20

SHEET


2 OF 7




FULL CIRCLE




FULL ELLIPSE (OVAL)




TOMBSTONE




TRAPEZOID




1/2 CIRCLE



OCTAGON



1/4 CIRCLE




TRIANGLE

NOTES:


1. SEE SHEET 6 FOR DETAILED ANCHOR INSTALLATION REQUIREMENTS.
2. THRU FRAME - MASONRY, WOOD OR METAL OPENING.
3. OVERALL SIZE MUST NOT EXCEED THE MAX. WIDTH AND HEIGHT OF RECTANGULAR WINDOWS ON SHEET 1.
4. ANCHOR SPACING FOR ARCHITECTURAL FLANGE WINDOWS MUST FOLLOW THE LAYOUT SHOWN ON SHEET 6, WITH ANCHOR SPACING MEASURED ALONG THE LENGTH OF THE PRODUCT.

DESIGN PRESSURES WITH GLASS TYPE A OR B GLAZING (DIMENSIONS ARE UNIT SIZES)

Short Side (in.)	Long Side (in.)									
	18	24	30	36	42	48	54	60	66	72
18	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5
24	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5
30	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+75.6/-75.6
36	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+74.8/-74.8	+66.5/-66.5
42	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+77.9/-77.9	+77.9/-77.9	+77.9/-77.9	+77.9/-77.9	+68.4/-68.4	+60.3/-60.3
48	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+77.9/-77.9	+59.7/-59.7	+59.7/-59.7	+59.7/-59.7	+59.7/-59.7	+56.1/-56.1
50	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+82.5/-82.5	+77.9/-77.9	+59.7/-59.7	+55.0/-55.0	+55.0/-55.0	+55.0/-55.0	+55.0/-55.0



GLASS TYPE A



GLASS TYPE B

NOTE: IF SIZE INTENDED IS NOT SHOWN, USE NEXT LARGER SIZE.

* SETTING BLOCKS PER FBC 2411.3.3.1




1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

**8150 PVC
PICTURE WINDOW
NON-IMPACT**

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF CUSTOM WINDOW SYSTEMS, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF CUSTOM WINDOW SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:
4093



8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering & Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:

**COMPARATIVE ANALYSIS
AND GLAZING DETAILS**

DRAWN BY: MCS	DATE: 8/3/2023
DWG #: CWS-506	REV.: E
SCALE: 1:1	SHEET 3 OF 7




1900 SW 44TH AVE.
 OCALA, FLORIDA 34474
 WWW.CWS.CC

**8150 PVC
 PICTURE WINDOW
 NON-IMPACT**

PROPRIETARY AND CONFIDENTIAL
 THE INFORMATION CONTAINED IN
 THIS DRAWING IS THE SOLE
 PROPERTY OF CUSTOM WINDOW
 SYSTEMS, INC. ANY
 REPRODUCTION IN PART OR AS A
 WHOLE WITHOUT THE WRITTEN
 PERMISSION OF CUSTOM WINDOW
 SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:
 4093






8/3/2023

LUCAS A. TURNER, P.E.
 FL PE # 58201
 Turner Engineering &
 Consulting, Inc.
 2428 Old Natchez Trc Trl
 Camden, TN 38320
 PH. 941-380-1574

SHEET DESCRIPTION:

SECTION VIEWS


DRAWN BY: MCS	DATE: 8/3/2023
DWG #: CWS-506	REV.: E
SCALE: 1:2	SHEET 4 OF 7




ITEMS NOT SHOWN FOR CLARITY:
 11-14

PARTS LIST			
ITEM	PART #	DESCRIPTION	MATERIAL
1	H-6222	FRAME W/FLANGE -SH	PVC
2	H-6222	FRAME W/ FLANGE -SH	PVC
3	H-6222	FRAME W/FLANGE -SH	PVC
4	H-6222	FRAME W/FLANGE -SH	PVC
5	S-6237	GLAZING BEAD, FIXED (7/8" O.A. I.G.)	PVC
8	S-6025	SASH STOP	PVC
9	P-3438	PURFECT GLAZE "H" OR SIKAFLEX 552	
10	P-5612	Setting Block, .12 x 1 x 2	Rubber
11		PW-8300 Gold Cert. Label, NFRC Tab	
13		NFRC LABEL, BLANK 4X8 LABEL	
14		LABEL, 9X9 CWS LOGO LABEL	
15		Glass, Fixed (See sheet 5)	


LINE ITEMS NOT USED:
6, 7, 12, 16



**PVC FRAME
FLANGE
H-6222**




**PVC SASH
STOP
S-6025**



**PVC GLAZING
BEAD
S-6237**

**FRAME CORNER
CONSTRUCTION**



**CORNER WELD
(ALL SIDES)
1:8**




1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

**8150 PVC
PICTURE WINDOW
NON-IMPACT**

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN
THIS DRAWING IS THE SOLE
PROPERTY OF CUSTOM WINDOW
SYSTEMS, INC. ANY
REPRODUCTION IN PART OR AS A
WHOLE WITHOUT THE WRITTEN
PERMISSION OF CUSTOM WINDOW
SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:
4093



8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering &
Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:
**DP CHART, BOM AND
EXTRUSIONS**

DRAWN BY: MCS	DATE: 8/3/2023
DWG #: CWS-506	REV.: E
SCALE: 1:1	SHEET 5 OF 7




1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

**8150 PVC
PICTURE WINDOW
NON-IMPACT**

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN
THIS DRAWING IS THE SOLE
PROPERTY OF CUSTOM WINDOW
SYSTEMS, INC. ANY
REPRODUCTION IN PART OR AS A
WHOLE WITHOUT THE WRITTEN
PERMISSION OF CUSTOM WINDOW
SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:
4093




8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering &
Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:
**ANCHOR SCHEDULE AND
NOTES**

DRAWN BY:	DATE:
MCS	8/3/2023
DWG #:	REV.:
CWS-506	E
SCALE:	SHEET
1:20	6 OF 7



ANCHOR LAYOUT - (FLANGE)

NOTES:

1. INSTALL ONE ANCHOR AT EACH INSTALLATION LOCATION. ANCHOR SPACING APPLIES TO ALL SHAPES (SEE SHEET 2) ALONG ALL FRAME EDGES. SILL ANCHOR SPACING SAME AS HEAD.
2. SHIM AS REQ AT EACH INSTALLATION ANCHOR USING LOAD BEARING SHIMS. MAX. ALLOWABLE SHIM STACK TO BE 1/4". USE SHIMS WHERE SPACE GREATER THAN 1/16" IS PRESENT. LOAD BEARING SHIMS SHALL BE CONSTRUCTED OF HIGH DENSITY PLASTIC OR BETTER. WOOD SHIMS ARE NOT ALLOWED.
3. ANCHOR TYPE, SIZE, SPACING AND EMBEDMENT SHALL BE AS SPECIFIED IN THESE DRAWINGS, SEE TABLE 1, SHEET 7.
4. ALL INSTALLATION ANCHORS MUST BE MADE OF OR PROTECTED WITH A CORROSION RESISTANT MATERIAL OR COATING. DISSIMILAR METALS OR MATERIALS IN CONTACT WITH PRESSURE TREATED WOOD MUST BE PROTECTED TO PREVENT REACTION.
5. INSTALLATION ANCHORS SHALL BE IN ACCORDANCE WITH ANCHOR MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND ANCHORS SHALL NOT BE USED IN SUBSTRATES WITH STRENGTHS LESS THAN THE MINIMUM SPECIFIED IN TABLE 1, SHEET 7.
6. ANCHOR EMBEDMENT TO SUBSTRATE SHALL BE BEYOND WALL DRESSING OR STUCCO. FOR CONCRETE/CMU OPENINGS, EMBEDMENT SHALL BE BEYOND WOOD BUCKS, IF USED, INTO SUBSTRATE - 1X BUCKS ARE OPTIONAL.
7. A MINIMUM CENTER-TO-CENTER SPACING SHALL BE MAINTAINED BETWEEN ALL FASTENERS: 3" FOR MASONRY, 1" FOR WOOD AND METAL.
8. WOOD OR MASONRY OPENINGS, BUCKS AND BUCK FASTENERS SHALL BE PROPERLY DESIGNED BY THE ARCHITECT OR ENGINEER OF RECORD AND INSTALLED TO TRANSFER WIND LOADS TO THE STRUCTURE. SUBSTRATES SHALL MEET THE MINIMUM STRENGTH REQUIREMENTS AS SHOWN IN TABLE 1, SHEET 7. CONCRETE AND MASONRY SUBSTRATES MAY NOT BE CRACKED.
9. SEALING AND FLASHING STRATEGIES FOR OVERALL WATER RESISTANCE OF INSTALLATION SHALL BE DONE BY OTHERS FOLLOWING THE CURRENT VERSION OF THE REFERENCE DOCUMENTS: FMA/AAMA 100(FIN WINDOWS), FMA/AAMA 200(FLANGE WINDOWS), FMA/WDMA 250(BOX WINDOWS), FMA/AAMA/WDMA 300(EXTERIOR DOORS)




1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

8150 PVC PICTURE WINDOW NON-IMPACT

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF CUSTOM WINDOW SYSTEMS, INC. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF CUSTOM WINDOW SYSTEMS, INC IS PROHIBITED.

FLORIDA APPROVAL NO.:

4093



8/3/2023

LUCAS A. TURNER, P.E.
FL PE # 58201
Turner Engineering & Consulting, Inc.
2428 Old Natchez Trc Trl
Camden, TN 38320
PH. 941-380-1574

SHEET DESCRIPTION:

INSTALLATION DETAILS

DRAWN BY:	DATE:
MCS	8/3/2023
DWG #:	REV.:
CWS-506	E
SCALE:	SHEET
1:2	7 OF 7

TYPICAL HEAD ANCHORAGE







TABLE 1: APPROVED INSTALLATION FASTENERS

SUBSTRATE TYPE	ANCHOR TYPE	MIN. EMBEDMENT	MIN. EDGE DIST.
CONCRETE (2.0 KSI MIN.)	3/16" ITW TAPCON	1-1/2"	1-1/8"
HOLLOW OR GROUT-FILLED CMU (117 PCF MIN.)	3/16" ITW TAPCON	1"	2"
CONCRETE (3.05 KSI MIN.)	3/16" DEWALT ULTRACON+	1-3/4"	1"
HOLLOW OR GROUT-FILLED CMU (ASTM C-90)	3/16" DEWALT ULTRACON+	1-1/4"	2-1/2"
2X MIN. SOUTHERN PINE (G=0.55)	3/16" ITW TAPCON OR DEWALT ULTRACON+	1-3/8"	7/8"
2X MIN. SOUTHERN PINE (G=0.55)	#10 WOOD SCREW	1-3/8"	7/8"
16 GAUGE (0.060") MIN. STEEL STUD (33 KSI YIELD MIN)	#10-16 HILTI KWIK-FLEX OR ITW TEKS SELF-DRILLING SCREW	FULL THREAD THRU 0.060"	7/16"
1/8" ALUM. (6063-T5 MIN.) OR 1/8" STEEL (33 KSI MIN.)	#10 GRADE 5 SELF-TAPPING / DRILLING SCREW	FULL THREAD THRU 0.125"	7/16"



B HORIZONTAL SECTION
7 TYPICAL JAMB ANCHORAGE



C HORIZONTAL SECTION
7 BOX FRAME INSTALLATION
HEAD AND SILL SIMILAR FOR BOX INSTALLATION

FLANGE REMOVAL NOTE: PARTIALLY OR FULLY REMOVING THE FLANGE, UP TO AND INCLUDING A BOX-FRAME APPLICATION IS ACCEPTABLE PROVIDED:

- MIN. 1/4" FILLET OF CONSTRUCTION-GRADE ADHESIVE CAULK IS APPLIED INSIDE AND OUT, FULL PERIMETER, BY INSTALLER.
- PRODUCT ANCHORAGE IS IN ACCORDANCE WITH REQUIREMENTS AS SHOWN FOR FLANGE WINDOWS.