


#### Jamb Attachment Notes:

- 1. Maximum Positive Load per Jamb = (10'-2" x 49.3 PSF) / 2 = 251 lbs. per foot.
- 2. Maximum Negative Load per Jamb = (10'-2" x -55.7 PSF) / 2 = 284 lbs. per foot.
- 3. Design of the supporting structure shall be the sole responsibility of the building designer and shall be designed for the jamb loads listed in notes 1 and 2.
- 4. Alternate jamb attachments may be used if approved by a registered Professional Engineer.
- 5. DASMA Technical Data Sheet TDS-161 may be used for alternate jamb attachments.
- 6. 3/8" diameter lag screws required 1/4" pilot hole and 1-1/2" minimum required distance.
- 7. Masonry fasteners by others.

2x6 Attachment to Structure						
Structure Type	Fastener Type	Minimum Embedment	Minimum Edge Distance		Maximum on Center Spacing	Allowable Tension Load
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8" OD Washer	2"	2.5	6"	24"	526
Southern Pine	3/8" x 3" Lag with 1-1/8" OD Washer	1.50"	1.50"	1.50"	24"	655
Spruce Pine Fir	3/8" x 3" LAG with 1-1/8" OD Washer	1.50"	1.50"	1.50"	23"	482






Scott A. Brown, P.E. Lic. No. 65940 Wendler Engineering Services, Inc. 698 Timber Creek Road, Dixon, IL 61021 FBPE CA Lic. No. 31544 Structural Adequacy for Wind Load


#### Typical Track Installation Bracket Mount Wood Jambs

Normal headroom track shown, low headroom, lift clearance and verical lift track available.



Treated 2x6 when mounting to masonry construction. Un-treated 2x6 may be used on wood construction.

Treated 2x6 #2 Douglas
Fir or better wood buck
when mounting to
masonry jambs. Un-treated
2x4 #2 Douglas Fir or better
may be used on wood jambs.
See chart for buck attachment
to structure.



Typical Track Installation Angle Mount Wood, Steel or Concrete Jambs


Normal headroom track shown, low headroom, lift clearance and verical lift track available.

Typical Track Installation Pre-Assembled Clip Angle Wood, Steel or Concrete Jambs

Normal headroom track shown, lift clearance and verical lift track available.


Scale: None		Title:			
Drawn by: R. Frey			Spec, Wi Energ		
Checked by: G. Wedekind	RAYNOR.		9.		
Date: 10/04/22	1101 East River Road	No.	P-2483	Sheet	Rev
ECO: 8593.03	Dixon, IL. 61021	INU.	F-2403	2	Α

Printed copies of this document are not considered signed and sealed and the SHA authentication code must be verified on any electronic copies.




Angle Mount					
Jamb Type	Fastener Type	Minimum Embedment (in.)	Minimum Edge Distance (in.)	Maximum on Center Spacing (in.)	Tension Load
	3/8" ITW Trubolt	2-1/2"	2-1/2"	36"	893
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8" OD Washer	2"	1-5/8"	18"	687
	1/4" x 2-5/8" Screw-Bolt+ with 9/16" OD Washer	2-1/2"	1-1/2"	18"	651
Steel	5/16" x 1" SAE J78, Min. AISI 1022 with 5/16" Washer	3/16"	1-1/2"	36"	971
Wood	5/16" x 1-3/4" Lag with 5/16" Washer	1-1/2"	1-1/2"	12"	352
Grout Filled CMU Block	3/8" Simpson Titen HD	2-3/4"	4"	18"	480

Alternate fasteners may be used if approved by a registered Professional Engineer.



### Track Assembly Attachment to 2500 PSI Min. Concrete

2" Angle mount turned-out standard (solid)
2" Angle mount turned-in optional (dashed)
3" Angle mount available




### Track Assembly Attachment to Wood Jamb

2" Angle mount turned-out standard (solid)
2" Angle mount turned-in optional (dashed)
3" Angle mount available




Scott A. Brown, P.E. Lic. No. 65940 Wendler Engineering Services, Inc. 698 Timber Creek Road, Dixon, IL 61021 FBPE CA Lic. No. 31544 Structural Adequacy for Wind Load



## Track Assembly Attachment to 3/16" Min. Steel Jamb

2" Angle mount turned-out standard (solid)
2" Angle mount turned-in optional (dashed)
3" Angle mount available




#### Track Assembly Attachment to Grout Filled CMU Block

2" Angle mount turned-out standard (solid)
2" Angle mount turned-in optional (dashed)
3" Angle mount available

Pre-Assembled Clip Angle					
Jamb Type	Fastener Type	Minimum Embedment (in.)	Minimum Edge Distance (in.)	Maximum on Center Spacing (in.)	Allowable Tension Load (Lbs.)
	3/8" ITW Trubolt	2-1/2"	2-1/2"	24"	893
2500 PSI Min. Concrete	1/4" Tapcon+ (Plus) with 1-1/8" OD Washer	2"	1-5/8"	24"	687
	1/4" x 2-5/8" Screw-Bolt+ with 9/16" OD Washer	2-1/2"	1-1/2"	24"	651
Steel	5/16" x 1" SAE J78, Min. AISI 1022 with 5/16" Washer	3/16"	1-1/2"	24"	971
Wood	5/16" x 1-3/4" Lag with 5/16" Washer	1-1/2"	1-1/2"	*12"	352
Grout Filled CMU Block	3/8" Simpson Titen HD	2-3/4"	4"	*12"	480


<sup>\*</sup> Field drilling reg'd.

Alternate fasteners may be used if approved by a registered Professional Engineer.




#### Pre-Assembled Track Assembly Attachment to 2500 PSI Min. Concrete

2" Clip angle turned-in standard (solid)
2" Clip angle turned-out optional (dashed)
3" Clip angle available




#### Pre-Assembled Track Assembly Attachment to Wood Jamb

2" Clip angle turned-in standard (solid)
2" Clip angle turned-out optional (dashed)
3" Clip angle available



### Pre-Assembled Track Assembly Attachment to 3/16" Min. Steel Jamb

2" Clip angle turned-in standard (solid)
2" Clip angle turned-out optional (dashed)
3" Clip angle available



# Pre-Assembled Track Assembly to Grout Filled CMU Block

2" Clip angle turned-in standard (solid)
2" Clip angle turned-out optional (dashed)
3" Clip angle available

Scale: None		
Drawn by: R. Frey		
Checked by: G. Wedekind		
Date: 10/04/22		
ECO: 8593.03		



Spec, V	√ind Load
Ener	gyCore

No. P-2483 Sheet 4