



# PRI Construction Materials Technologies LLC

6412 Badger Drive  
Tampa, FL 33610  
813.621.5777  
<https://www.pri-group.com/>

## Laboratory Test Report

**Report for:** Petersen Aluminum  
1234 Gardiner Lane  
Louisville, KY 40213

**Product Name(s):** 24ga. 16" Steel - Board and Batten Wall Panels

**Project No.:** 2651T0007A

**Date(s) Tested:** April 11<sup>th</sup> – May 1<sup>st</sup>, 2024

**Test Methods:** TAS 202 (ASTM E330) & TAS 203 & ASTM A370 (Tensile)

**MD Notification:** PRI2420599

**Results Summary:** Wind Load Resistance: +120/-112psf

**Purpose:** Evaluate the wind load resistance and tensile strength of the Petersen’s 24ga steel Board and Batten 16" wall panel cladding system in accordance with Testing Application Standard (TAS) 202 Criteria for Testing Impact & Non-Impact Resistant Building Envelope Components Using Uniform Static Air Pressure/ASTM E330 Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Difference, Testing Application Standard (TAS) 203 Criteria for Testing Products Subject to Cyclic Wind Pressure Loading, and ASTM A370 Standard Test Methods and Definitions for Mechanical Testing of Steel Products.

**Test Methods:** Testing was completed as described in Testing Application Standard (TAS) 202-94 Criteria for Testing Impact & Non-Impact Resistant Building Envelope Components Using Uniform Static Air Pressure / ASTM E330-14 (2021) Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Difference, Testing Application Standard (TAS) 203-94 Criteria for Testing Products Subject to Cyclic Wind Pressure Loading, and ASTM A370-21 Standard Test Methods and Definitions for Mechanical Testing of Steel Products. Test methods assigned or referenced include, ASTM E1886 Standard Test Method for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Missile(s) and Exposed to Cyclic Pressure Differentials, and ASTM E8 Standard Test Methods for Tension Testing of Metallic Materials.

**Sampling:** The following materials were received by PRI. All other materials for testing were procured by PRI-CMT through local distribution.

<u>Product</u>	<u>Source</u>	<u>Date</u>	<u>Sampling</u>
16" 24ga Steel Board & Batten Panels (57.8 ksi)	Elg Grove, Village, IL	Feb. 23 <sup>rd</sup> , 2024	Petersen Aluminum
#10-13 x 1" GP Concealor Pancake Head Screws			

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

**Assembly Detail:** The test assemblies were constructed on 56" wide by 96" tall walls, fabricated from nominal 2x12 SYP perimeter framing members with 2x6 SYP wooden intermediate framing members spaced 16" O.C. (See Appendix A for details) The framing was sheathed with nominal 15/32" plywood and attached with 8D nails; 6" O.C. around the perimeter and in the field. Three (3) 2" diameter holes were fabricated in each stud cavity through the sheathing to permit pressurization to the back side of the cladding panels. Polyethylene film and tape was applied between the back of the panels and the plywood sheathing prevent excess air leakage during negative loading. (Film was cut for positive loads.)

**System Details:** Each assembly was constructed with three full (3) panels, one (1) starter strip (cut from a panel), and one (1) fabricated panel. A 96" length of starter strip was attached to the vertical edge of the assembly with each adjacent panel slid into the corresponding interlock. The starter strip and each panel was attached into the sheathing only with fourteen (14) #10-13 x 1" GP Concealor screws spaced approximately 6-1/2" O.C. into each nail flange slot.

**Testing Location:** Testing was conducted at PRI-CMT located in Tampa, FL. Verification of testing instrumentation was performed by either an ISO accredited calibration laboratory or by a PRI-CMT representative in compliance with PRI-CMT In-House quality control program governed by ISO/IEC 17025-17.

*Continued on the next page...*

2651T0007A

---

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

**Test Results:** Conditions at the beginning of testing were 23°C (73°F) with 50% Rh.

Table 1: Results TAS 202 / ASTM E330 Positive Loading.

Test Method	Test Pressure	Allowable	Recorded Measurement <sup>3</sup>	Result <sup>4</sup>		
½ Uniform Load Structural  TAS 202/E330 ½ Test Load <sup>1,2</sup>	+90 psf	Deflection			Pass	
		Report Only	Specimen 1	0.03"		
			Specimen 2	0.01"		
			Specimen 3	< 0.01"		
Uniform Load Deflection  TAS 202/E330 Design Pressure <sup>1,2</sup>	+120 psf	Deflection			Pass	
		Report	Specimen 1	0.03"		
			Specimen 2	0.02"		
			Specimen 3	< 0.01"		
		Permanent Set – Allowable = 90% Recovery				Pass
		≤ 0.01"	Specimen 1	< 0.01"		
			Specimen 2	< 0.01"		
Specimen 3	< 0.01"					
Uniform Load Structural  TAS 202/E330 Full Test Load <sup>1,2</sup>	+180 psf	Deflection			Pass	
		Report Only	Specimen 1	0.05"		
			Specimen 2	0.03"		
			Specimen 3	< 0.01"		
		Permanent Set – Allowable = 90% Recovery				Pass
		≤ 0.01"	Specimen 1	< 0.01"		
			Specimen 2	< 0.01"		
Specimen 3	< 0.01"					

Notes:

1. Loads were held for 30 seconds.
2. Tape and polyethylene film were utilized to seal the specimen for excessive air leakage, and in the PRI-CMT witness's opinion did not influence the test results
3. Deflection and permanent set were captured on the midspan of the center panel, the unsupported span measured 16". See Appendix A Sketches for gauge measurement locations.
4. Upon completion of testing the specimen did not have indication of deterioration or incipient failure, such as cracking, fastener loosening, local yielding exceeding 10% over maximum deflection, or loss of adhesive bond.

*Continued on the next page...*

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

Table 2: Results TAS 202 / ASTM E330 Negative Loading.

Profile	Loading Data				
	Test Pressure (psf) <sup>1</sup>	Load Duration (sec)	Test Specimen		
			1	2	3
16" 24Ga Steel Board & Batten Panels	130	30	Pass	Pass	Pass
	135	30	Pass	Pass	Pass
	140	30	Pass	Pass	Pass
	145	30	Pass	Pass	Pass
	150	30	Pass	Pass	Pass
	160	30	Pass	Pass	Pass
	170	30	Pass	Pass	Pass
	180	30	Pass	Pass	Pass
	185	30	Pass	Pass	Pass
	190	30	Pass	Pass	Pass
	195	30	Pass	Pass	Pass
	200	30	Pass	Pass	Pass
	205	30	Pass	Pass	Pass
	210	30	Pass	Pass	Pass
	215	30	Pass	Pass	Pass
	220	30	Pass	Pass	Fail <sup>2</sup>
	225	30	Pass	Pass	-
	230	30	Fail <sup>2</sup>	Pass	-
235	30	-	Pass	-	
240	30	-	Fail <sup>2</sup>	-	

Notes:

1. Incremental Pressure Differential loading was specified by the client. Negative pressure only.
2. Failure due to anchor withdrawal resulting in panel disengagement/buckle. See Appendix A Photographs.

Average Passing Pressure 3 Specimens <sup>1</sup>	225 PSF
Average Ultimate Failure 3 Specimens <sup>1</sup>	230 PSF

Notes:

1. Individual specimen results did not exceed ±15 of the base three average.

Continued on the next page...

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

Table 3: Specimens 4 -6 - TAS 203 / E1886 Results

Direction	Pressure Differential	Number of Cycles Completed	Specimen	Max Deflection <sup>1</sup>	Permanent Set <sup>1</sup>	Result <sup>2</sup>
Positive	24 to 60 psf	3500	4	0.02"	0.01"	Pass
			5	0.05"	0.01"	Pass
			6	0.03"	0.01"	Pass
	0 to 72 psf	300	4	0.02"	0.01"	Pass
			5	0.05"	0.01"	Pass
			6	0.02"	0.01"	Pass
	60 to 96 psf	600	4	0.04"	< 0.01"	Pass
			5	0.04"	0.01"	Pass
			6	0.03"	0.01"	Pass
	36 to 120 psf	100	4	0.06"	0.01"	Pass
			5	0.01"	0.01"	Pass
			6	0.02"	< 0.01"	Pass
Negative	-34 to -112 psf	50	4	0.82"	0.01"	Pass
			5	1.27"	0.17"	Pass
			6	0.92"	0.11"	Pass
	-56 to -90 psf	1050	4	0.77"	0.07"	Pass
			5	0.93"	0.15"	Pass
			6	0.90"	0.21"	Pass
	0 to -67 psf	50	4	0.74"	0.08"	Pass
			5	0.88"	0.21"	Pass
			6	0.85"	0.25"	Pass
	-25 to -56 psf	3350	4	0.66"	0.09"	Pass
			5	0.77"	0.15"	Pass
			6	0.78"	0.19"	Pass

Notes:

1. Deflection and permanent set were captured on the midspan of the center panel, the unsupported span measured 16". See sketch (Assembly 1) in Appendix A for gauge measurement locations.
2. Upon completion of testing the specimen met the requirements outlined in the Florida Building Code section 1626.2.8.

*Continued on the next page...*

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

Table 4: ASTM A379/E8 Results

Physical Properties	Test Method	Results			Requirement
		Tensile Strength	Yield Strength	Elongation @ Break	
Tensile (ksi / %) 3 Samples 8" x 1/2" x Thickness As Received; Rate 0.1 in/min Test @ 73.4±3.6°F;	ASTM A370 ASTM E8	57.8	53.2	37.3	Report


Note(s): None


**Statement of Compliance:**

Testing was conducted in accordance with methods designated in Testing Application Standard (TAS) 202-94 Criteria for Testing Building Envelop Components Using Uniform Static Pressure, Testing Application Standard (TAS) 203-94 Criteria for Testing Products Subject to Cyclic Wind Pressure Loading, and ASTM E330-14(2021) Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Difference. Upon completion the test samples resisted the wind loading corresponding to +120 & -112 pressure differentials. This report does not constitute certification of this product which may only be granted by the certification program administrator. The laboratory test results presented in this report are representative of the material supplied.

Signed:   
Timothy Efaw  
Manager

Date: 05/20/2024

Signed:   
Zachary Priest - PE  
Director



Date: 05/21/2024

**Report Issue History:**

Issue #	Date	Pages	Revision Description (if applicable)
Original	05/20/2024	10	NA


Appendix Follows...

2651T0007A


The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

### Sketches

#### Framing Details



#### Anchoring Details




Continued on the next page...

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

### Deflection / Permanent Set Measurement



*Continued on the next page...*

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.



## Photographs

### Assembly Prior to Test (Typical)




*Continued on the next page...*

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.

### Typical Failure



Fastener Withdrawal

Panel Disengagement/Buckle

**END OF REPORT**

2651T0007A

The laboratory test results presented in this report are based on the material(s) supplied and tested. The results, and by extension any statements of conformity, opinions, or interpretations, apply the "simple acceptance" decision rule for measurement uncertainty accounting. This report is for the exclusive use of stated client. Only the client is authorized to permit copying or distribution of this report and then only in its entirety. PRI Construction Materials Technologies LLC assumes no responsibility nor makes a performance or warranty statement for this material or products and processes containing this material in connection with this report.